

SUMMARY OF QUANTITIES				80% FED 20% STATE		
CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE:		
				I000 URBAN BEGINNING OF PROJECT TO WHIPPLE ROAD	I000 RURAL WHIPPLE ROAD TO END OF PROJECT	SFTY-2A URBAN SN 019-2017
20400800	FURNISHED EXCAVATION	CU YD	55	32	23	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	94	12	82	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,277	5251	6016	10
40600300	AGGREGATE (PRIME COAT)	TON	276	128	148	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	18	21	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	65	30	35	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5037	2080	2952	5
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	972	583	389	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11,105	5191	5904	10
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	867	339	528	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	119,179	46,942	72,117	120
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20927	17940	2987	
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	760	760		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	100		100	
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	FOOT	7545	7545		
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	1189	386	803	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12,266	5997	6269	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	451	451		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	69,392	36,176	33,216	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	10,075	4894	5181	

SUMMARY OF QUANTITIES				80% FED 20% STATE		
CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE:		
				I000 URBAN BEGINNING OF PROJECT TO WHIPPLE ROAD	I000 RURAL WHIPPLE ROAD TO END OF PROJECT	SFTY-2A URBAN SN 019-2017
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	3251	3081	170	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2013	2013		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	333	333		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1397	700	697	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	451	451		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	91,779	36,176	55,603	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10,075	4894	5181	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3251	3081	170	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2013	2013		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	333	333		
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	647	387	260	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	647	387	260	
88500100	INDUCTIVE LOOP DETECTOR	EACH	24	24		
88600100	DETECTOR LOOP, TYPE 1	FOOT	3065	3065		
XX007274	LEVELING BINDER (MACHINE METHOD), SPECIAL	TON	85	85		
X8860100	LOOP DETECTOR TESTING	EACH	3	3		

△ REVISED