

F.L. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
613	(B) RS-5	BUREAU	22	3
STA.		TO STA.		
FED. ROAD DIST. NO.	BLINDS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			80% FED. 20% STATE
CODE NO.	ITEM	UNIT	I000 TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	49
20400800	FURNISHED EXCAVATION	CU YD	12
25000210	SEEDING, CLASS 2A	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10
25100630	EROSION CONTROL BLANKET	SQ YD	436
35100100	AGGREGATE BASE COURSE, TYPE A	TON	9
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5983
40600300	AGGREGATE (PRIME COAT)	TON	151
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22
40600525	LEVELING BINDER (HAND METHOD), N50	TON	36
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	2503
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1162
40600990	TEMPORARY RAMP	SQ YD	415
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5906
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	443
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	60101
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	12552
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	16
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	84
44213100	PAVEMENT FABRIC	SQ YD	100
44213200	SAW CUTS	FOOT	186
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	138
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1667
48203100	HOT-MIX ASPHALT SHOULDERS	TON	76
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	206
60255500	MANHOLES TO BE ADJUSTED	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2
63200310	GUARDRAIL REMOVAL	FOOT	200
63300205	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	112.5
63300905	VERTICAL ADJUSTMENT OF GUARD RAIL, TYPE A	FOOT	662.5
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1

SUMMARY OF QUANTITIES (CONTINUED)			80% FED. 20% STATE
CODE NO.	ITEM	UNIT	I000 TOTAL QUANTITY
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8036
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	214.8
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	68333
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3981
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	632
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	666
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	194
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	936
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	214.8
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9631
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	151
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	632
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	666
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	194
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	58702
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	3830
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	363
78200300	PRISMATIC CURB REFLECTOR	EACH	16
78200410	GUARDRAIL MARKERS, TYPE A	EACH	11
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	362
Z0017100	DOWEL BARS	EACH	60
Z0075300	TIE BARS	EACH	20

\* SPECIALTY ITEMS

Mar 17, 2008 - 10:35:40 AM  
c:\projects\ed01507\cvr\shf.dgn