

F.A. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
613	(B) RS-5	BUREAU	22	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PERMANENT PAVEMENT MARKINGS												
LOCATION	DESCRIPTION	PAINT PAVEMENT MARKING			THERMOPLASTIC PAVEMENT MARKING							
		YELLOW 4"	WHITE 4"	YELLOW 6"	LETTERS & SYMBOLS	YELLOW 4"	WHITE 4"	WHITE 6"	WHITE 8"	YELLOW 12"	WHITE 12"	WHITE 24"
		FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
698+54 TO 703+54	DBL NO PASS	1000	1000									
703+54 TO 713+50	LEFT NO PASS	996	1992	250								
713+50 TO 724+34			2168	270								
724+34 TO 731+10	RIGHT NO PASS	767	1534	190								
731+10 TO 733+47	DBL NO PASS	474	474									
733+47 TO 745+10	LEFT NO PASS	1163	2326	290								
745+10 TO 763+30			3640	460								
763+30 TO 772+50	RIGHT NO PASS	920	1840	230								
772+50 TO 789+70	DBL NO PASS	3440	3440									
789+70 TO 802+67	LEFT NO PASS	1297	2594	320								
802+67 TO 825+55			4576	570								
825+55 TO 833+20	RIGHT NO PASS	765	1530	190								
833+20 TO 841+52	DBL NO PASS	1664	1664									
841+52 TO 843+42	MEDIAN & ISLAND					554	456		189	36	140	36
944+34 TO 951+58	MEDIAN & TURN LANE				31.2	2484	1332		100	150		
951+58 TO 960+00	MEDIAN & TURN LANE				46.8	3035	1410		163	340		
960+00 TO 960+30	DBL NO PASS	60	60									
960+30 TO 965+44	LEFT NO PASS	514	1028	130								
965+44 TO 966+34			180	20								
966+34 TO 970+24	RIGHT NO PASS	390	780	100								
970+24 TO 972+55	RIGHT NO PASS	231	231	60								
972+55 TO 1001+50	DBL NO PASS	5790										
1001+50 TO 1005+47	DBL NO PASS	794	794									
1005+47 TO 1010+03	LEFT NO PASS	456	912	110								
1010+03 TO 1034+35			4864	610								
1034+35 TO 1035+53	RIGHT NO PASS	118	236	30								
550 EAST ST (CR 29)	STOP BAR											21
988+90 TO 994+71	PARALLEL PARKING						144					
995+00 TO 996+25	DIAGONAL PARKING						216					
MAIN ST	CROSSWALK & STOP BAR							151				36
1002+60 RT	R X R				68.4							36
1005+86 LT	R X R				68.4							36
1500N AVE (TR 645E)	ISLAND & STOP BAR								180		80	29
SUB TOTALS		20839	37863	3830	214.8	6073	3558	151	632	526	140	194
TOTALS		58702	3830	214.8	9631	151	632	666	194			

REFLECTORS SCHEDULE					
LOCATION	DESCRIPTION	PRISMATIC CURB REFLECTOR	RAISED REFLECT PVMT MARKER	RAISED REFLECT PVMT MARKER	RAISED REFLECT PVMT MARKER
			AMBER	CRYSTAL	REM
			EACH	EACH	EACH
RTE 34					
698+54 TO 842+27	MAINLINE		180		180
842+27 TO 843+06	S MEDIAN		8		8
SE Quad	ISLAND	8			
RTE 6					
944+34 TO 951+05	W MEDIAN		34		34
949+97 TO 951+00	W TURN LANE			3	3
952+13 TO 960+00	E MEDIAN		42		42
952+23 TO 954+00	E TURN LANE			5	4
1021+30	TR645 E ISLAND	8			
960+00 TO 1035+53	MAINLINE		91		91
SUB TOTALS		16	355	8	362
TOTALS		16	363		362

PATCHING SCHEDULE						
STATION	CLASS B PATCHES		TIE BARS EACH	PVMT FABRIC SQ YD	DOWEL BARS EACH	SAW CUTS FOOT
	TY III 13"	TY IV 13"				
	SQ YD	SQ YD				
NBL						
830+67		26		26	20	57
838+98	16			16	20	50
SBL						
839+11		58	20	58	20	79
TOTALS	16	84	20	100	60	186

STATION EQUATION
 STA 951+69.52 US 34 / US 6 (AH)
 = STA 843+76.59 US 34 (BK)

Mar 14, 2008 - 10:26:01 AM
 c:\projects\ed01507\cvr\shf.dgn