

## SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:

SFTY-2A

RURAL  
100% STATE  
TOTAL  
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
X0321468	PLUG EXISTING DECK DRAINS	EACH	44
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	519
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	24
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	161
Z0018905	DRILL AND GROUT BARS	EACH	36
Z0032470	JOINT SEALER	FOOT	78
Z0050400	REMOVE AND REPLACE ANCHOR BOLTS	EACH	1
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	1

FILE NAME = c:\projects\main09\cm305\details.dgn	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED - 03/21/2008
		DRAWN - RON WOODSHANK	REVISED - 03/21/2008
		CHECKED - ---	REVISED - ---
		DATE - ---	REVISED - ---
PLOT SCALE = 41.3612' / IN.		PLOT DATE = Apr 02, 2008 - 10:15:53 AM	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

### SUMMARY OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET NO. 4 OF 4 SHEETS STA. 571+00.67 TO STA. 573+01.17

F.A.P. RTE. 846	SECTION 66B-111	COUNTY GRUNDY	TOTAL SHEETS 29	SHEET NO. 7
CONTRACT NO. 66728				
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				