

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: Y007

RURAL
100% STATE
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	64
20400800	FURNISHED EXCAVATION	CU YD	164
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	50
50102400	CONCRETE REMOVAL	CU YD	3.4
50200100	STRUCTURE EXCAVATION	CU YD	100
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	360
54003000	CONCRETE BOX CULVERTS	CU YD	3.4
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	46

FILE NAME = c:\projects\main09\con306\details.dgn	USER NAME = carpenterdj	DESIGNED - R..WOODSHANK	REVISED - ---
		DRAWN - R..WOODSHANK	REVISED - ---
PLOT SCALE = 1/8" = 1' / IN.	CHECKED - ---	REVISED - ---	REVISED - ---
PLOT DATE = Mar 05, 2008 - 11:47:13 AM	DATE - ---	REVISED - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 3 OF 6 SHEETS STA. _____ TO STA. _____

F.A.S. RTE. 296	SECTION (G.F.I)	COUNTY GRUNDY	TOTAL SHEETS 11	SHEET NO. 3
FED. ROAD DIST. NO. - ILLINOIS			CONTRACT NO. 66742	