

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE SFTY-2A
20200100	EARTH EXCAVATION	CU YD	53.3	53.3
42001200	PAVEMENT FABRIC	SQ YD	331	331
44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	350	350
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.2	2.2
60602800	CONCRETE GUTTER, TYPE B	FOOT	350	350
63000135	STEEL PLATE BEAM GUARD RAIL, TYPE B (SPECIAL)	FOOT	316	316
63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	1	1
63200310	GUARDRAIL REMOVAL	FOOT	350	350
67100100	MOBILIZATION	L SUM	1	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1220	1220
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	80	80
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	5	5
78300100	PAVEMENT MARKING REMOVAL	SQ FT	328	328
X4832450	PORTLAND CEMENT CONCRETE SHOULDERS 11" (SPECIAL)	SQ YD	331	331
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1

\* SPECIALTY ITEM

FILE NAME = c:\projects\main09\cm307\details.dgn	USER NAME = woodsherk-1	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 317	SECTION (221)-1	COUNTY IROQUOIS	TOTAL SHEETS 13	SHEET NO. 3
PLOT SCALE = 1/8" = 100' / IN.		CHECKED - ---	REVISED - ---	SCALE: -----		STA. 1380+00 TO STA. 1393+00		CONTRACT NO. 66755		
PLOT DATE = Mar 27, 2008 - 08:27:53 AM		DATE - -----	REVISED - ---	FED. ROAD DIST. NO. - ILLINOIS STATE AID PROJECT						