

RESURFACING SCHEDULE									
LOCATION	LENGTH	HMA SURF REM 1 1/2"	HMA SURF CSE	TEMP RAMP	BIT MAT (PR CT)	AGG (PR CT)	MIX FOR CRACKS, JTS & FLGWYS	LEVEL BINDER (H.M.)	AGG SHLDR
STA TO STA		SQ YD	TON	SQ YD	GAL	TON	TON	TON	TON
1625+55 TO 1661+32.8	3577.8	12126	1019	151	970	24	4	6	136
TOTAL	3577.8	12126	1019	151	970	24	4	6	136

NOTE: AGG SHOULDER QUANTITY HAS BEEN INCLUDED FOR USE IN AREAS WITH LOW EXISTING SHOULDER

SHOULDER SCHEDULE				
LOCATION	WIDTH	LENGTH	PAVED SHLDR REM	HMA SHLDR 8"
STA TO STA			SQ YD	SQ YD
1629+00 TO 1632+10 LT	3'	310	103	103
1625+55 RT TO 1632+60 RT	6'	705	470	470
TOTAL		1015	573	573

THERMOPLASTIC PAVEMENT MARKING SCHEDULE						
LOCATION	LENGTH	THERMOPLASTIC PAVEMENT MARKING 4 INCH		THERMO PVMT MARK 6 INCH	THERMO PVMT MARK 8 INCH	RAISED REFLECT PVMT MARKER
		WHITE	YELLOW	YELLOW	WHITE	EACH
		FOOT	FOOT	FOOT	FOOT	
1625+55 TO 1661+32.8	3577.8	7156	383	894	180	51
SUBTOTAL		7156	383	894	180	51
TOTAL			7539	894	180	51

SHORT-TERM PAVEMENT MARKING SCHEDULE			
LOCATION	LENGTH	SHORT-TERM PAVEMENT MARKING	WORK ZONE PVMT MARKING REMOVAL
		FOOT	SQ FT
		1625+55 TO 1661+32.8	3577.8
TOTAL		716	119