

GENERAL NOTES

(Revised October 5, 2006)

THE THICKNESS OF HMA SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA IS PLACED.

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HMA LIFTS.

SHORT TERM PAVEMENT MARKING SHALL BE USED TO OUTLINE EXIT AND ENTRANCE RAMPS FOR THE PRIME COAT APPLICATION AND EACH RESURFACING LIFT.

ON EXISTING PAVEMENT WHICH MAY BE SUPERELEVATED, THE NEW HMA PAVEMENT SHALL BE BUILT WITH THE SAME SUPERELEVATION UNLESS NEW SUPERELEVATION RATES ARE GIVEN ON THE PLANS. ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
BITUMINOUS MAT PRIME COAT	0.08	GAL / SQ YD OR
	0.375	GAL / SQ YD
AGGREGATE PRIME COAT	0.002	TONS / SQ YD
HMA RESURFACING	112	LBS / SQ YD / IN
SHORT TERM PAVEMENT MARKING	10	FT / 100 FT OF APPLICATION
MIX FOR CRACKS, JTS & FLGWYS	0.0003	TONS / SQ YD
LEVEL BINDER (HAND METHOD)	0.0005	TONS / SQ YD

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE SHALL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	90% FED. 10% STATE
			1000 TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2460
40600300	AGGREGATE (PRIME COAT)	TON	62
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10
40600545	LEVELING BINDER (HAND METHOD), N90	TON	15
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	3726
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	2911
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	3286
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	8448
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	19608
48203017	HOT-MIX ASPHALT SHOULDERS, 5"	SQ YD	600
67100100	MOBILIZATION	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4594
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1516
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45936
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4256
78000620	THERMOPLASTIC PAVEMENT MARKING - LINE 18"	FOOT	12
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	106
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	106
Xo 325 702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1

• SPECIALTY ITEMS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Rich Fawell
DISTRICT STUDIES & PLANS ENGINEER

DATE: 3-19-08

EXAMINED BY: [Signature]
DISTRICT CONSTRUCTION ENGINEER

[Signature]
DISTRICT MATERIALS ENGINEER

[Signature]
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = brcbayac	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
ca:\projects\4366774\4366774-shr-cover.dgn	DRAWN -	REVISED -	80			INTERMITTANT RESURFACING 2008	LASALLE	6	2
PLOT SCALE = 47.8261' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66774						
PLOT DATE = Mar 18, 2008 - 04:24:46 PM	DATE -	REVISED -	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT						