

MAINLINE SCHEDULE											
LOCATION MILE MARKERS		CENTERLINE REPAIR HMA SURF REM SPECIAL	EDGE LINE REPAIR HMA SURF REM SPECIAL	HOT-MIX ASPH. SURF. REM 2"	HOT-MIX ASPH. SURF. REM 5"	POLY. HOT-MIX ASPH. SURF. MIX E N105	POLY. HOT-MIX ASPH. BINDER IL-19.0 N105	BIT MATL PR CT	AGG PR CT	MIX FOR CR, JTS, & FLANGEWAYS	LEVEL BINDER (HM)
	LENGTH	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	GAL	TON	TON	TON
LASALLE COUNTY											
EASTBOUND DRIVING LANE											
72.9 TO 74.1**	6336		470			53		37.6	0.9	0.14	0.24
91.9 TO 92.2	1584			2112		237		169.0	4.2	0.63	1.06
92.4 TO 92.5	528			704		79		56.3	1.4	0.21	0.35
98.5 TO 98.9	2112				2816	237	552	225.3	5.6	0.84	1.41
99.8 TO 100	1056				1408	118	276	112.6	2.8	0.42	0.70
EASTBOUND PASSING LANE											
91.9 TO 92.2	1584			2112		237		169.0	4.2	0.63	1.06
92.4 TO 92.5	528			704		79		56.3	1.4	0.21	0.35
WESTBOUND DRIVING LANE											
72.9 TO 74.1	6336	1408	1408			315		225.3	5.6	0.84	0.70
92.2 TO 92.4	1056			1408		158		112.6	2.8	0.42	0.70
92.6 TO 92.8	1056			1408		158		112.6	2.8	0.42	0.70
94.4 TO 94.6	1056				1408	118	276	112.6	2.8	0.42	0.70
94.7 TO 95	1584				2112	177	414	169.0	4.2	0.63	1.06
98.2 TO 98.4	1056				1408	118	276	112.6	2.8	0.42	0.70
99 TO 99.3	1584				2112	177	414	169.0	4.2	0.63	1.06
99.7 TO 99.9*	1056				1408	118	276	112.6	2.8	0.42	0.70
100.4 TO 100.5	528				704	59	138	56.3	1.4	0.21	0.35
101.5 TO 101.8	1584				2112	177	414	169.0	4.2	0.63	1.06
102.9 TO 103	528				704	59	138	56.3	1.4	0.21	0.35
WESTBOUND PASSING LANE											
95.7 TO 96	1584				2112	177	414	169.0	4.2	0.63	1.06
100.8 TO 100.9	528				704	59	138	56.3	1.4	0.21	0.35
TOTAL	33264	1408	1878	8448	19008	2911	3726	2459.4	61.5	9.22	14.67

* LOOPS IN PAVEMENT IN THIS AREA-OMIT-DO NOT DISTURB-SEE DETAIL
 **WORK IN THIS AREA (MM 72.9 TO MM 74.1 (EBL, DL)) IS THE 2' SPECIAL MILLING AT THE EDGE OF PAVEMENT. THE WORK IS NOT FOR THE ENTIRE 1.2 MILES, BUT AT VARIOUS LOCATIONS WITHIN THIS SECTION-MAINLY WHERE THE RAMP MEETS THE MAINLINE

SHOULDER REPAIR*		
LOCATION MILE MARKERS	HMA SURF. REM	HMA SHLD
	5" SQ YD	5" TON
LASALLE COUNTY		
VARIOUS LOCATIONS	600	600
TOTAL	600	600

* THIS ITEM IS A CONTINGENCY ITEM TO REPAIR
 HMA SHOULDER DUE TO TRAFFIC DAMAGE TO SHOULDER
 DURING PAVING OF MAINLINE

PAVEMENT MARKING SCHEDULE							
LOCATION STATION TO STATION		THERMO PVMT MARK LINE 4"	THERMO PVMT MARK LINE 6"	RAISED REFLEC PVT MK	RAISED REFLEC PVT MK REMO	SHORT-TERM PVMT. MARK.	WORK-ZONE PVMT. MARK. REM.
	LENGTH	FOOT	FOOT	EACH	EACH	FOOT	SQ FT
LASALLE COUNTY							
EASTBOUND DRIVING LANE							
72.9 TO 74.1	6336	6336				634	209
91.9 TO 92.2	1584	1584				158	52
92.4 TO 92.5	528	528				53	17
98.5 TO 98.9	2112	2112				211	70
99.8 TO 100	1056	1056				106	35
EASTBOUND PASSING LANE							
72.9 TO 74.1	6336	6336	1600	40	40	634	209
91.9 TO 92.2	1584	1584	396	10	10	158	52
92.4 TO 92.5	528	528	132	3	3	53	17
WESTBOUND DRIVING LANE							
72.9 TO 74.1	6336	6336				634	209
92.2 TO 92.4	1056	1056				106	35
92.6 TO 92.8	1056	1056				106	35
94.4 TO 94.6	1056	1056				106	35
94.7 TO 95	1584	1584				158	52
98.2 TO 98.4	1056	1056				106	35
99 TO 99.3	1584	1584				158	52
99.7 TO 99.9	1056	1056				106	35
100.4 TO 100.5	528	528				53	17
101.5 TO 101.8	1584	1584				158	52
102.9 TO 103	528	528				53	17
WESTBOUND PASSING LANE							
72.9 TO 74.1	6336	6336	1600	40	40	634	209
95.7 TO 96	1584	1584	396	10	10	158	52
100.8 TO 100.9	528	528	132	3	3	53	17
TOTAL	45936	45936	4256	106	106	4594	1516