

PATCHING SCHEDULE - WESTBOUND LANES

LOCATION M.P.	PASSING LANE							DRIVING LANE						
	CLASS B PATCHING			DOWEL BARS EACH	SAW CUTS FOOT	PVMT FABRIC SQ YD	TIE BARS EACH	CLASS B PATCHING			DOWEL BARS EACH	SAW CUTS FOOT	PVMT FABRIC SQ YD	TIE BARS EACH
	TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD					TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				
73.00	LASALLE/BUREAU COUNTY LINE													
72.90	13			20	56	13								
72.89								8			20	48	8	
72.85		20		20	66	40								
72.84	8			20	48	8		8			20	48	8	
72.80	8			20	48	8								
72.40	8			20	48	8								
72.48	13			20	56	13		13			20	56	13	
72.20	13			20	56	13		13			20	56	13	
72.19								11			20	52	11	
72.10	11			20	52	11		11			20	52	11	
71.70			27	20	76	54	10			67	20	136	134	25
71.75	13			20	56	13		13			20	56	13	
71.50			53	20	116	106	20			53	20	116	106	20
71.20	8			20	48	8		8			20	48	8	
71.19	8			20	48	8		8			20	48	8	
70.15	IL ROUTE 89													
WB TOTALS	103	20	80	260	774	303	30	93		120	220	716	333	45

FILE NAME = c:\projects\cm388\details.dgn	USER NAME = carpentardj	DESIGNED <i>RLW</i>	REVISED -
		DRAWN <i>RLW</i>	REVISED -
PLOT SCALE = 103.4829' / IN.	CHECKED -		REVISED -
PLOT DATE = Mar 08, 2008 - 08:53:44 AM	DATE -		REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES - PROJECT 2

SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.I. RTE. 80	SECTION D3 PAVEMENT PATCHING	COUNTY BUREAU	TOTAL SHEETS 13	SHEET NO. 9
FED. ROAD DIST. NO. ILLINOIS		CONTRACT NO. 66778		