

PAVEMENT MARKING												
LOCATION STA TO STA	DESCRIPTION	LENGTH FOOT	PAINT PAVEMENT MARKING			TEMP PAINT PAVT MARKING			SHORT TERM PVT MKG FOOT	WORK ZONE PAVT MKING REMOVAL SQ FT	RAISED REFLEC PAVT MKR EACH	RAISED REFL PAVT MKR REMOVAL EACH
			LINE 4"		LINE 6"	LINE 4"		LINE 6"				
			WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	YELLOW FOOT				
CENTERLINES												
8+22.2 TO 14+52	DOUBLE SOLID	629.8		1260			1260		252	441	9	9
14+52 TO 20+83	SOLID LT, DASH RT	631		631	160		631	160	252	311	8	8
20+83 TO 33+60	DASH	1277			320			320	511	203	16	16
33+60 TO 44+10	DASH LT, SOLID RT	1050		1050	260		1050	260	420	515	13	13
44+10 TO 60+76	SOLID LT, DASH RT	1666		1666	420		1666	420	666	821	21	21
60+76 TO 66+00	DASH	524			130			130	210	82	7	7
66+00 TO 77+70	DASH LT, SOLID RT	1170		1170	290		1170	290	468	574	15	15
77+70 TO 87+60	SOLID LT, DASH RT	990		990	250		990	250	396	488	12	12
87+60 TO 99+16	DASH LT, SOLID RT	1156		1156	290		1156	290	462	569	14	14
99+16 TO 111+84	DOUBLE SOLID	1268		2536			2536		507	888	16	16
111+84 TO 122+12	SOLID LT, DASH RT	1028		1028	260		1028	260	411	507	13	13
122+12 TO 125+33	DASH	321			80			80	128	51	4	4
125+33 TO 131+39	DASH LT, SOLID RT	606		606	150		606	150	242	297	8	8
131+39 TO 143+66.3	DOUBLE SOLID	1227.3		2455			2455		491	859	16	16
143+66.3 TO 144+91.7	BRIDGE OMISSION STR NO 019-0033											
144+91.7 TO 146+35	DOUBLE SOLID	143.3		287			287		57	100	3	3
146+35 TO 148+53	SOLID LT, DASH RT	218		218	50		218	50	87	105	3	3
148+53 TO 169+13	DASH	2060			520			520	824	329	26	26
169+13 TO 172+45.0	DASH LT, SOLID RT	332		332	80		332	80	133	162	5	5
EDGELINES												
8+22.2 TO 143+66.3	SOLID LT & RT	13544.1		27088			27088			9029		
143+66.3 TO 144+91.7	BRIDGE OMISSION STR NO 019-0033											
144+91.7 TO 172+45.0	SOLID LT & RT	2753.3		5507			5507			1836		
SUB-TOTALS				32595	15384		32595	15384				
TOTALS				47979	3260		47979	3260	6519	18166	208	208

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\projects\4366802\4366802-sht-cover.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -						557	128RS-4	DEKALB	11	6
	PLOT DATE = Mar 24, 2008 - 02:26:00 PM	CHECKED -	REVISED -						CONTRACT NO. 66802				
				SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					