

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	90
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	326
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	22.1
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	13.1
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	463
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	66
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	235
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	319
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	319
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	590
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	150
78300100	PAVEMENT MARKING REMOVAL	SQ FT	268
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	469
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	79
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	4
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEM

FILE NAME =	USER NAME = woodshenkr1	DESIGNED - RLW	REVISED - ----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\projects\deck beam repl 00\sn 032-0034.dgn		DRAWN - RLW	REVISED - ----			623	10-BR-111	GRUNDY	12	3	
PLOT SCALE = 1/8" = 1'-0"		CHECKED - ----	REVISED - ----			CONTRACT NO. 66808					
PLOT DATE = Mar 27, 2008 - 09:05:49 AM		DATE - ----	REVISED - ----			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					