

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

RURAL
100% STATE
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	68
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	246
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	23.9
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	4.3
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	600
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	70.9
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	200
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	263
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	87
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	134
78300100	PAVEMENT MARKING REMOVAL	SQ FT	154
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	600
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	34
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEM

FILE NAME :	USER NAME : woodshankr1	DESIGNED - RLW	REVISED - ----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\projects\deck beam repl 08\en 038-012.dgn		DRAWN - RLW	REVISED - ----			681	(1178R)I	ILLINOIS	13	3	
PLOT SCALE : 183.5775 ' / IN.		CHECKED - ----	REVISED - ----			CONTRACT NO. 66817					
PLOT DATE : Mar 27, 2008 - 10:27:03 AM		DATE - ----	REVISED - ----			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____