

URBAN

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
				Knox Co. Fed 80-State20 X271-2A				
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	321.5	321.5				
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1374.6	1374.6				
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	392.9	392.9				
40600215	POLYMERIZED BITUMINOUS MATERIAL (PRIME COAT)	TON	0.3	0.3				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1333.9	1333.9				
40600990	TEMPORARY RAMP	SQ YD	478	478				
40603540	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	236.8	236.8				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	675.7	675.7				
42001300	PROTECTIVE COAT	SQ YD	1457.7	1457.7				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	678.9	678.9				
44000100	PAVEMENT REMOVAL	SQ YD	169.1	169.1				
44000700	APPROACH SLAB REMOVAL	SQ YD	848	848				
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	629.2	629.2				
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	78.3	78.3				
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	87.4	87.4				
44213000	PATCHING REINFORCEMENT	SQ YD	165.7	165.7				

FILE NAME	USER NAME = lqymedm	DESIGNED -	REVISED -
S:\GEN\DRAF\STD&PLNS\Squad\68216	Person\general.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/19/2008	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	(21-HB-11)	KNOX	55	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 68216	