

**GUARD RAIL SCHEDULE**

**TRAFFIC BARRIER TERMINAL**

LOCATION	Remove & Reinstall				SPBGR Type A	GR MKRS Type A*
	SPBGR Ty A	Type 2	Type 5	Type 6		
WB 493+15 to 495+15 (outside)		1	1		175	4
WB 494+64 to 494+90 (inside)		1	1			
WB 497+25 to 501+00 (inside)	50			1	275	4
WB 497+53 to 499+77 (outside)	50			1	125	4
EB 492+36 to 494+49 (outside)	50			1	125	4
EB 491+01 to 494+76 (inside)	50			1	275	4
EB 496+87 to 498+87 (outside)		1	1		175	4
EB 497+12 to 497+39 (inside)		1	1			
<b>TOTAL</b>	200 lin ft	4 each	4 each	4 each	1150 lin ft	24 each

**GUARDRAIL REMOVAL**

LOCATION	LIN FT
<b>EBL</b>	
493+61 to 494+61 (outside)	100
493+71 to 494+71 (inside)	100
497+06 to 499+18 (outside)	212
<b>WBL</b>	
493+73 to 495+10 (outside)	138
496+57 to 497+32 (inside)	75
497+65 to 498+40 (outside)	75
<b>TOTAL</b>	<b>700 LF</b>

**BARRIER WALL MARKER TYPE C\***

LOCATION	EACH
SN 048-0021	8
SN 048-0022	8
<b>TOTAL</b>	<b>16</b>

\*monodirectional crystal

**EPOXY PAVEMENT MARKING**

LOCATION	4" EDGE		6" SKIP		8" SOLID	
	W	Y	W	W	W	W
WB 492+85 to 499+78	693	693	340		360	
EB 492+40 to 499+18	678	678	340		215	
<b>RAMP GORES</b>					<b>300</b>	
<b>TOTAL</b>			<b>680 LF</b>		<b>875 LF</b>	

**CHANGEABLE MESSAGE SIGN**

LOCATION	SIGNS	CAL MO
WB on US 150	1	3
EB on US 150	1	3
<b>TOTAL</b>	<b>2</b>	<b>6</b>

used in conjunction with TC&P Std 701423  
for the Henderson Street lane closures required for painting.

**PAVEMENT MARKING TAPE T3 4"**

LOCATION	LIN FT
TC&P 701402	9556
TC&P 701411	820
TC&P 701423	4440
<b>TOTAL</b>	<b>14816</b>

**PAVEMENT MARKING REMOVAL**

LOCATION	SQ FT
NB GORE US 150	80.5
SB GORE US 150	80.5
STAGE I US 34	501
STAGE II US 34	683
<b>TOTAL</b>	<b>1345</b>