



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2008

SUBJECT: FAP Route 313 (US 34)
Project ACF-0313 (019)
Section 6RS-2
Henderson County
Contract No. 68342
Item No. 243, June 13, 2008 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised sheet 5 of the Fold-Up Plans.
3. Revised page i of the Table of Contents to the Special Provisions.
4. Added pages 35 - to to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 4; Mike Renner; Estimates

TBW:RS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 68342

State Job # - C-94-038-03
 PPS NBR - 4-00105-0000
 County Name - HENDERSON--
 Code - 71 - -
 District - 4 - -
 Section Number - 6RS-2

Project Number
 ACF-0313/019/

Route
 FAP 313

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* X0322729	MATL TRANSFER DEVICE	TON	5,384.000				
X4067107	POL LB MM IL4.75 N50	TON	2,692.000				
40600200	BIT MATLS PR CT	TON	34.400				
40600300	AGG PR CT	TON	197.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	570.000				
40600990	TEMPORARY RAMP	SQ YD	829.000				
40603540	P HMA SC "D" N70	TON	5,384.000				
40800050	INCIDENTAL HMA SURF	TON	172.000				
44000152	HMA SURF REM 3/4	SQ YD	37,677.000				
44000157	HMA SURF REM 2	SQ YD	26,155.000				
44201811	CL D PATCH T1 14	SQ YD	59.000				
44201815	CL D PATCH T2 14	SQ YD	846.000				
44201819	CL D PATCH T3 14	SQ YD	227.000				
44201821	CL D PATCH T4 14	SQ YD	424.000				
			* REVISED : MAY 28, 2008				

ROUTE		SECTION	COUNTY	SHEET	
F.A.P.	313	GRS-2	HENDERSON	TOTAL	NO.
MKD.	U.S. 34			22	5

100%
80% FED.
20% STATE
CONTRACT NO: 68342

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,114.0
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	78.0
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	55,994.0
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	345.0
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	247.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	670.0
*	EPOXY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	78.0
*	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	55,994.0
*	EPOXY PAVEMENT MARKING-LINE 8"	FOOT	345.0
*	EPOXY PAVEMENT MARKING-LINE 12"	FOOT	247.0
*	RAISED REFLECTIVE PAVEMENT MARKER	EACH	303.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	273.0
△ X0322129	MATERIAL TRANSFER DEVICE	TON	5,384

* SPECIALTY ITEMS
△ REVISED 5-28-08

SUMMARY OF QUANTITIES

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
AGGREGATE QUALITY	1
DELAYED START OF MULTIPLE CONTRACTS	2
PLACEMENT OF HOT-MIX ASPHALT SURFACE COURSES	2
HOT-MIX ASPHALT SURFACE COURSE SURFACE TESTS	3
HOT-MIX ASPHALT SURFACE REMOVAL, ¾" AND 2"	3
PAVEMENT DRAINAGE AFTER COLD MILLING	5
TRAFFIC CONTROL PLAN	6
WORK ZONE PAVEMENT MARKINGS ON MILLED SURFACES	6
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	6
EPOXY PAVEMENT MARKINGS (BDE)	14
EQUIPMENT RENTAL RATES (BDE)	15
HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE)	16
HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE)	17
HOT-MIX ASPHALT – TRANSPORTATION (BDE)	19
HOT-MIX ASPHALT MIXTURE IL-4.75 (BDE)	19
PAYMENTS TO SUBCONTRACTORS (BDE)	24
RECLAIMED ASPHALT PAVEMENT (RAP) (BDE)	25
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE)	31
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	31
WORKING DAYS (BDE)	32
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)	32
MATERIAL TRANSFER DEVICE (BDE)	35

Revised 06/02/2008

MATERIAL TRANSFER DEVICE (BDE)

Effective Date: June 15, 1999

Revised Date: January 1, 2007

Description. This work shall consist of placing HMA surface course mixtures according to Section 406 of the Standard Specifications, except that these materials shall be placed using a material transfer device.

Materials and Equipment. The material transfer device shall have a minimum surge capacity of 15 tons (13.5 metric tons), shall be self-propelled and capable of moving independent of the paver, and shall be equipped with the following:

- (a) Front-Dump Hopper and Conveyor. The conveyor shall provide a positive restraint along the sides of the conveyor to prevent material spillage.
- (b) Paver Hopper Insert. The paver hopper insert shall have a minimum capacity of 14 tons (12.7 metric tons).
- (c) Mixer/Agitator Mechanism. This re-mixing mechanism shall consist of a segmented, anti-segregation, re-mixing auger or two full-length longitudinal paddle mixers designed for the purpose of re-mixing the hot-mix asphalt (HMA). The longitudinal paddle mixers shall be located in the paver hopper insert.

CONSTRUCTION REQUIREMENTS

General. The material transfer device shall be used for the placement of all HMA surface placed with paver excluding shoulder, side roads, mailbox turnouts and entrances. The material transfer device speed shall be adjusted to the speed of the paver to maintain a continuous, non-stop paving operation.

The material transfer device will be permitted on partially completed segments of full-depth HMA pavement if the thickness of binder in place is 10 in. (250 mm) or greater.

Structures. The material transfer device may be allowed to travel over structures under the following conditions:

- (a) Approval will be given by the Engineer.
- (b) The vehicle shall be emptied of HMA material prior to crossing the structure and shall travel at crawl speed across the structure.
- (c) The tires of the vehicle shall travel on or in close proximity and parallel to the beam and/or girder lines of the structure.

Method of Measurement. This work will be measured for payment in tons (metric tons) for surface course materials placed with a material transfer device.

Added 06/02/2008

Basis of Payment. This work will be paid for at the contract unit price per ton (metric ton) for MATERIAL TRANSFER DEVICE.

The various HMA mixtures placed with the material transfer device will be paid for as specified in their respective specifications. The Contractor may choose to use the material transfer device for other applications on this project; however, no additional compensation will be allowed.

Added 06/02/2008