

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	82	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

*13R-1:(9)TS:(12)BL,1-1

SUMMARY OF QUANTITIES

URBAN

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	I000 80/20	Y031-1F MARGRET & 2ND ST. 80/20	Y031-1F ANN ELIZA & 2ND ST. 80/15/5	Y030-1E 80/20	SFTY-2A 80/20
25100630	EROSION CONTROL BLANKET	SQ YD	726	726				
28000400	PERIMETER EROSION BARRIER	FOOT	2,155	2,155				
28000500	INLET AND PIPE PROTECTION	EACH	14	14				
35100100	AGGREGATE BASE COURSE, TYPE A	TON	370	370				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1				
40600300	AGGREGATE (PRIME COAT)	TON	5	5				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	187	187				
40600990	TEMPORARY RAMP	SQ YD	115	115				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL.-19.0, N50	TON	870	870				
40603565	<i>POLYMERIZED</i> HOT-MIX ASPHALT SURFACE CRSE, MIX "E", N70	TON	136	136				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10				
42000501	<i>← PAVEMENT 10" (JOINTED) PORTLAND CEMENT CONCRETE</i>	SQ YD	5,592	5,592				
42300300	<i>← DRIVEWAY PAVEMENT, 7 INCH PORTLAND CEMENT CONCRETE</i>	SQ YD	66	66				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK <i>4 INCH</i>	SQ FT	5,047	5,047				
42400800	DETECTABLE WARNINGS	SQ FT	60	60				
44000100	PAVEMENT REMOVAL	SQ YD	5,671	5,671				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, <i>2"</i>	SQ YD	1,407	1,407				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	117	117				
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	2,500	2,500				
44000600	SIDEWALK REMOVAL	SQ FT	5,029	5,029				
44002805	ISLAND REMOVAL	SQ FT	275	275				
60255500	MANHOLES TO BE ADJUSTED	EACH	7	7				
60260100	INLETS TO BE ADJUSTED	EACH	7	7				
60605000	COMBINATION CONCRETE CURB <i>AND</i> GUTTER, TYPE B-6.24	FOOT	2,500	2,500				
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	2,478	2,478				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1				
* 63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO.	5	5				

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____