

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	82	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*13R-1(9)TS:(12)BL,I-1

SUMMARY OF QUANTITIES

URBAN

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	I000 80/20	Y031-1F MARGRET & 2ND ST. 80/20	Y031-1F ANN ELIZA & 2ND ST. 80/15/5	Y030-1E 80/20	SFTY-2A 80/20
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	5	5				
67100100	MOBILIZATION	L SUM	1	1				
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,012	1,012				
70300610	TEMP PAINT PAVEMENT MARKING, LETTERS ^{AND} SYMBOLS	SQ FT	262	262				
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	1,563	1,563				
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	690	690				
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	1,111	1,111				
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	677	677				
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	221	221				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	287	287				
* 78003100	PREFORMED PLASTIC TYPE B - LETTERS ^{AND} SYMBOLS ^{PAVEMENT MARKING,}	SQ FT	262	262				
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1,563	1,563				
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	690	690				
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	1,111	1,111				
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	677	677				
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	221	221				
* 78100100	RAISE REFLECTIVE PAVEMENT MARKER	EACH	8	8				
78300200	RAISE REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8				
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	1		0.5	0.5		
* 81012600	CONDUIT IN TRENCH, 2" DIAMETER, PVC	FOOT	352	8	195	149		
* 81012800	CONDUIT IN TRENCH, 3" DIAMETER, PVC	FOOT	75		75			
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4		2	2		
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	2,370	939	546	885		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	352	8	195	149		

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY