

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	82	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

\*13R-1(9)TS(12)BL-1-1

SUMMARY OF QUANTITIES

URBAN

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 80/20	Y031-1F MARGRET & 2ND ST. 80/20	Y031-1F ANN ELIZA & 2ND ST. 80/15/5	Y030-1E 80/20	SFTY-2A 80/20
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4				4	
* 83004200	LIGHT POLE, ALUMINUM, 50 FT. M.H., 6 FT. DAVIT ARM	EACH	4				4	
* 83800650	BREAKWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	16				16	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	590.5		269	321.5		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1219		590.5	628.5		
* 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	138			138		
* 87502630	TRAFFIC SIGNAL POST, ALUMINUM 9 FT.	EACH	3		1	2		
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1			
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1			
* 87702530	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 34 FT. AND 36 FT.	EACH	1			1		
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	40		22	18		
87900100	DRILL EXISTING FOUNDATION	EACH	1	1				
87900200	DRILL EXISTING HANDHOLE	EACH	5	1	4			
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		4	4		
* 88102810	PEDISTRAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4		2	2		
* 88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	8		4	4		
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	324		66	258		
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		2	2		
89502380	REMOVE EXISTING HANDHOLE	EACH	6		2	4		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4		2	2		
* X0324132	VIDEO CONTROL CABINET AND EQUIPMENT	L SUM	1	1				
X0325542	HIGH EARLY STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"(JOINTED)	SO YD	80	80				
X0712400	TEMPORARY PAVEMENT	SO YD	275	275				
X0919000	TEMPORARY PAVEMENT REMOVAL	SO YD	275	275				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	63	63				
X8110170	REPAIR EXISTING CONDUIT ATTACHED TO STRUCTURE	L SUM	1				1	
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	469.5	469.5				
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO.6 IC	FOOT	993	469.5	264.5	259		

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_ HORIZ. \_\_\_\_\_ DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_ CHECKED BY \_\_\_\_\_