

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693		TAZEWELL	82	18
IL 9				

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

*13R-1(9)TS(12)BL.1-1

PAVEMENT REMOVAL	
LOCATION	SQ YD
IL 9 (EB)	
STA. 105+88 TO STA. 109+13	1,124.7
STA. 109+38 TO STA. 110+36.22	402.95
IL 9 (WB)	
STA. 105+83 TO STA. 109+10	1009.86
STA. 109+59 TO STA. 112+20	904.04
SECOND STREET	
STA. 8+50 TO STA. 14+05.6	2,229.88
TOTAL	5,671

PERIMETER EROSION BARRIER	
LOCATION	FOOT
SECOND ST.	
RT. STA. 10+25 TO STA. 12+20	195
LT. STA. 8+85 TO ANN ELIZA LT. STA. 111+00	205
LT. STA. 10+50 TO MARGARET ST LT. STA. 110+45	250
IL 9 (WB) / ANN ELIZA ST.	
RT. STA. 105+83 TO STA. 108+80	275
LT. STA. 105+83 TO STA. 108+80	515
RT. STA. 110+00 TO STA. 111+30	130
IL 9 (EB) / MARGARET ST.	
RT. STA. 105+89 TO STA. 107+93.8	285
LT. STA. 105+89 TO STA. 108+89	300
TOTAL	2,155

CONCRETE MEDIAN, TYPE SB-6.24	
LOCATION	SQ FT
NW CORNER OF SECOND ST & ANN ELIZA	315.99
SE CORNER OF SECOND ST & ANN ELIZA	430.74
NE CORNER OF SECOND ST & MARGARET	291.15
SW CORNER OF SECOND ST & MARGARET	1,440
TOTAL	2,478

PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	
LOCATION	SQ YD
IL 9 (EB)	
STA. 105+88 TO STA. 109+13	1,124.7
STA. 109+38 TO STA. 110+36.22	370.95
IL 9 (WB)	
STA. 105+83 TO STA. 109+10	1009.86
STA. 109+59 TO STA. 112+20	856.04
SECOND STREET	
STA. 8+50 TO STA. 14+05.6	2,229.88
TOTAL	5,592

TEMPORARY PAVEMENT	
LOCATION	SQ YD
NW CORNER OF SECOND ST & ANN ELIZA	35.11
SE CORNER OF SECOND ST & ANN ELIZA	47.86
NE CORNER OF SECOND ST & MARGARET	32.35
SW CORNER OF SECOND ST & MARGARET	160
TOTAL	275

HIGH-EARLY STRENGTH PCC PAVEMENT 10 INCH (JOINTED)	
LOCATION	SQ. YD.
IL 9 (EB)	
LT. STA. 109+11 TO STA. 109+23 (STAGE 1)	16
RT. STA. 109+23 TO STA. 109+35 (STAGE 3)	16
IL 9 (WB)	
RT. STA. 109+03 TO STA. 109+57.83 (STAGE 1)	17.33
LT. STA. 109+57.83 TO STA. 109+80 (STAGE 3)	30.67
TOTAL	80

TEMPORARY PAVEMENT REMOVAL	
LOCATION	SQ YD
NW CORNER OF SECOND ST & ANN ELIZA	35.11
SE CORNER OF SECOND ST & ANN ELIZA	47.86
NE CORNER OF SECOND ST & MARGARET	32.35
SW CORNER OF SECOND ST & MARGARET	160
TOTAL	275

ISLAND REMOVAL	
LOCATION	SQ YD
NW CORNER OF SECOND ST & ANN ELIZA	35.11
SE CORNER OF SECOND ST & ANN ELIZA	47.86
NE CORNER OF SECOND ST & MARGARET	32.35
SW CORNER OF SECOND ST & MARGARET	160
TOTAL	275

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
IL 9 (EB) STA. 110+36.22 TO STA. 113+21	8
TOTAL	8

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
IL 9 (EB) STA. 110+36.22 TO STA. 113+21	8
TOTAL	8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY