

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	•	TAZEWELL	82	20
IL 9				
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

•13R-1:(9)TS;(12B)L,I-1

PORTLAND CEMENT CONCRETE SIDEWALK, 4"	
LOCATION	SQ FT
SECOND ST. LT. STA. 8+74 TO LT. STA. 9+83	568.18
ANN ELIZA LT. STA. 109+75 TO LT. STA. 112+01	874.9
ANN ELIZA RT. STA. 112+80 TO RT. STA. 110+35	942.5
SECOND ST. LT. STA. 10+10 TO LT. STA. 11+62	940.14
MARGARET ST. LT. STA. 109+49 TO LT. STA. 110+36.22	616.24
MARGARET ST. RT. STA. 110+36.22 TO RT. STA. 109+53	416.1
SECOND ST. LT. STA. 12+72 TO RT. STA. 14+05.6	688.18
TOTAL	5047

SIDEWALK REMOVAL	
LOCATION	SQ FT
SECOND ST. LT. STA. 8+74 TO LT. STA. 9+83	568.18
ANN ELIZA LT. STA. 109+75 TO LT. STA. 112+01	857.97
ANN ELIZA RT. STA. 112+80 TO RT. STA. 110+35	942.5
SECOND ST. LT. STA. 10+10 TO LT. STA. 11+62	940.14
MARGARET ST. LT. STA. 109+49 TO LT. STA. 110+36.22	616.24
MARGARET ST. RT. STA. 110+36.22 TO RT. STA. 109+53	416.1
SECOND ST. LT. STA. 12+72 TO RT. STA. 14+05.6	688.18
TOTAL	5029

EROSION CONTROL BLANKET	
LOCATION	SQ YD
LT STA. 110+37 (IL 9 WB) TO RT STA. 111+38 (IL 9 WB)	138.67
LT STA. 8+50 (2ND ST) TO LT STA. 112+00 (IL 9 WB)	109.5
LT STA. 105+83 (IL 9 WB) TO RT STA. 9+00 (2ND ST)	120.67
RT STA. 105+83 (IL 9 WB) TO RT STA. 11+00 (2ND ST)	143.88
LT STA. 105+88 (IL 9 EB) TO RT STA. 11+00 (2ND ST)	143.88
RT STA. 105+88 TO RT STA. 107+93.8 (IL 9 EB)	68.67
TOTAL	726

INLET AND PIPE PROTECTION	
LOCATION	EACH
SECOND ST.	
RT. 11' STA. 10+30.4	1
RT. 9' STA. 12+22.3	1
RT. 1' STA. 12+51	1
RT. 8' STA. 12+84	1
IL 9 (WB) / ANN ELIZA ST.	
LT. 16' STA. 108+32.4	1
RT. 30.8' STA. 110+00	1
LT. 14' STA. 111+97.7	1
RT. 22' STA. 112+15	1
RT. 3' STA. 109+08.5	1
RT. 7' STA. 109+67.3	1
RT. 3' STA. 111+61.3	1
IL 9 (EB) / MARGARET ST.	
LT. 16' STA. 108+70.8	1
RT. 15' STA. 109+03.7	1
RT. 13' STA. 109+43.1	1
TOTAL	14

PCC DRIVEWAY PAVEMENT 7"	
LOCATION	SQ YD
SECOND ST.	
LT. STA. 13+23 TO LT. STA. 13+53	16.11
LT. STA. 13+70 TO LT. STA. 13+88	8
IL 9 (WB) / ANN ELIZA ST.	
RT. STA. 111+57 TO RT. STA. 112+02	25
IL 9 (EB) / MARGARET ST.	
RT. STA. 109+72 TO RT. STA. 110+02	16.67
TOTAL	66

DETECTABLE WARNINGS	
LOCATION	SQ FT
ANN ELIZA	
NW CORNER LT. 14.78' STA. 109+70.69	6
SW CORNER RT. 36.66' STA. 109+90.91	6
ISLAND RT. 11.64' STA. 109+72.70	6
ISLAND RT. 22.92' STA. 109+76.82	6
FRONT ST	
NW CORNER LT. 18.61' STA. 111+64.67	6
NE CORNER LT. 17.21' STA. 111+17.31	6
MARGARET ST.	
NW CORNER LT. 36.04' STA. 109+64.2	6
SW CORNER RT. 25.04' STA. 109+47.33	6
ISLAND LT. 19.84' STA. 109+50.09	6
ISLAND LT. 11.41' STA. 109+48.09	6
TOTAL	60

DRIVEWAY PAVEMENT REMOVAL	
LOCATION	SQ YD
SECOND ST.	
LT. STA. 8+82 TO LT. STA. 9+12	16.67
LT. STA. 11+00 TO LT. STA. 11+28	15.56
LT. STA. 13+23 TO LT. STA. 13+53	16.11
LT. STA. 13+70 TO LT. STA. 13+88	8
IL 9 (WB) / ANN ELIZA ST.	
RT. STA. 110+35 TO RT. STA. 110+69	18.89
RT. STA. 111+57 TO RT. STA. 112+02	25
IL 9 (EB) / MARGARET ST.	
RT. STA. 109+72 TO RT. STA. 110+02	16.67
TOTAL	117

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY