

SUMMARY OF QUANTITIES

F. A. L. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D4 DIR REPAIR	WOODFORD	9	3
STA.		TO STA.		
FED. ROAD DIST. NO. 6		BLANKS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		WOODFORD CO. 100% STATE J000					
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	978	978					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	489	489					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1467	1467					
28000400	PERIMETER EROSION BARRIER	FOOT	300	300					
35100200	AGGREGATE BASE COURSE, TYPE A	CU YD	489	489					
42100300	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	1467	1467					
42100900	PAVEMENT REINFORCEMENT 10"	SQ YD	1467	1467					
44000100	PAVEMENT REMOVAL	SQ YD	1467	1467					
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	333	333					
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	333	333					
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3					
60100070	SHOULDER REMOVAL AND REPLACEMENT	FOOT	20	20					
60107600	PIPE UNDERDRAINS 4"	FOOT	1100	1100					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	81	81					
63300205	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	13	13					
67100100	MOBILIZATION	L SUM	1	1					
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2					

*SPECIALTY ITEM