

REMOVE & REINSTALL OF EXISTING SPBGR, TYPE A	
Location	Foot
SBL	
Lt. Sta. 457 + 94 - 458 + 07	13
Total	13

(for Construction of PIPE UNDERDRAINS 4", SPECIAL)

PERIMETER EROSION BARRIER	
Location	Foot
SBL	
Lt. Sta. 585 + 00 - 588 + 00	300
Total	300

PAVEMENT MARKING TAPE, TYPE III, 4"	
Location	Foot
SBL	
Sta. 452 + 60 - 466 + 38	2716
Sta. 583 + 60 - 605 + 38	2416
Total	5132

WORK ZONE PAVEMENT MARKING REMOVAL	
Location	Sq Ft
SBL	
Sta. 452 + 60 - 466 + 38	805.3
Sta. 583 + 60 - 605 + 38	905.3
Total	1711

TEMPORARY CONCRETE BARRIER	
Location	Foot
SBL	
Sta. 454 + 00 - 464 + 38	1038
Sta. 585 + 00 - 590 + 38	538
Total	1576

PAVEMENT MARKING REMOVAL	
Location	Sq Ft
SBL	
Sta. 452 + 60 - 464 + 38	392.7
Sta. 583 + 60 - 590 + 38	226
Total	619

IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
Location	Each
SBL	
Sta. 464 + 38	1
Sta. 590 + 38	1
Total	2

(Design Speed 55mph)

TIE BARS 3/4"	
Location	Each
SBL	
Sta. 454 + 00 - 462 + 00	530
Sta. 585 + 00 - 588 + 00	98
Total	628

TRAFFIC CONTROL & PROTECTION STANDARD 701402	
Location	Each
JOBSITE	2
Total	2

FILE NAME =
S:\GEN\DRAWING\STD&PLNS\Squed\168705 1-3

USER NAME = brucebn
nplans.dgn
PLOT SCALE = 200.0000 ' / IN.
PLOT DATE = 3/25/2008

DESIGNED - ---
DRAWN - ---
CHECKED - ---
DATE - -----

REVISED - ---
REVISED - ---
REVISED - ---
REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D4 DIP REPAIR 2008	WOODFORD	8	7
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				

CONTRACT NO. 68705