



SYMBOLS

- Arrow board
- Work area
- Sign
- Direction indicator barricade with steady burn monodirectional light
- Type II drum with steady burn monodirectional light
- Temporary concrete barrier
- Monodirectional barrier wall/guardrail marker
- Impact attenuator

- ① Temporary pavement marking tape shall be placed throughout the taper and along-side the work area. The right edge line shall be white and the left edge line shall be yellow.
- ② Barrier wall/guardrail markers at 7.6 m (25'). Markers on right shall be white and markers on left shall be amber.

NORMAL POSTED SPEED	FORMULAS
	Metric English
45 mph or more	$L = 0.65WS$ $L = WS$
	W = Width of offset in meters (feet).
	S = Normal posted speed in mph.

All dimensions are in millimeters (inches) unless otherwise shown.

FILE NAME =	USER NAME = brucebm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LANE CLOSURE DETAILS BETWEEN WORK AREAS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
S:\GEN\DRIFT\STD&PLNS\Squad\168705 1-3	plens.dgn	DRAWN -	REVISED -			39	D4 DIP REPAIR 2008	WOODFORD	9	8	
	PLOT SCALE = 200.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 68705					
	PLOT DATE = 3/28/2008	DATE -	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					