

EXCAVATION AND GRADING EXISTING SHOULDER

LOCATION	CUT (CU YD)	FILL (CU YD)	QUANTITIES (UNIT)
SECTION A:			
W.B.			
LT STA 58+50 TO 69+50	79	80	11
LT STA 69+50 TO 83+00	145	138	14
LT STA 83+00 TO 94+00	181	113	11
LT STA 94+00 TO 106+00	162	85	12
LT STA 106+00 TO 118+00	177	80	12
LT STA 118+00 TO 129+00	196	71	11
LT STA 129+00 TO 134+00	46	46	5
SECTION B:			
W.B.			
LT STA 10+00 TO 45+47	485	551	35
LT STA 45+47 TO 81+56	1422	404	36
LT STA 81+56 TO 117+57	1842	419	36
LT STA 117+57 TO 142+03	1801	701	24
SUB-TOTAL	6,536.00	2,688	
TOTAL			208

TRAFFIC CONTROL AND PROTECTION STANDARDS

LOCATION	STANDARD	QUANTITIES (L. SUM)
SECTION A & B:		
W.B. & E.B.	701401	1

MOBILIZATION

LOCATION	QUANTITIES (L. SUM)
SECTION A & B:	
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	QUANTITIES (CAL MO)
SECTION A & B:	
4 MESSAGE SIGNS X 3 CAL. MONTHS PER SIGN	12
TOTAL	12

TEMPORARY IMPACT ATTENUATOR

LOCATION	QUANTITIES (EACH)
SECTION A:	
W.B.	
TO BE USED AT STRUCTURES FOR SHOULDER WIDENING WHEN S.P.B.G.R. IS DOWN	2
TOTAL	2

ENGINEERING FIELD OFFICE TYPE A

LOCATION	QUANTITIES (CAL MO)
SECTION A & B:	
TOTAL	3.50

IMPACT ATTENUATOR SEVERE USE (NARROW)

LOCATION	QUANTITIES (EACH)
SECTION A:	
W.B.	
LT STA. 76+50 TO 76+81	1
LT STA. 95+13 TO 94+44	1
TOTAL	2

FILE NAME =	USER NAME = brucebm	DESIGNED -	REVISED -
C:\Projects\safety\174marton\cover sheet.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(90-15)J	TAZEWELL	192	13
CONTRACT NO. 68724			ILLINOIS FED. AID PROJECT	