

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
653	1051-1	PUTNAM	24	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

67100100 MOBILIZATION					
LOCATION					L SUM
STA.	to	STA.			
45+00		200+00			1
TOTAL					1

70100460 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306					
LOCATION					L SUM
STA.	to	STA.			
45+00		200+00			1
TOTAL					1

70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326					
LOCATION					L SUM
STA.	to	STA.			
45+00		200+00			1
TOTAL					1

70103815 TRAFFIC CONTROL SURVEILLANCE					
LOCATION					CAL DA
STA.	to	STA.			
45+00		200+00			20
TOTAL					20

63300205 REM. AND REIN. OF EXIST. STEEL PLATE BEAM GUARD RAIL, TYPE A					
LOCATION			Typical Section	Qty.	
STA.	to	STA.			FT.
LT	7915.5		4		250.0
LT	8234.23	8429	4		194.8
LT	12283	12463	4		180.0
LT	13302	13387	4		85.0
RT	8001	8165.5	4		164.5
RT	8234.23	8484.23	4		250.0
RT	12228	12478	4		250.0
Total					1374.3

X0301512 GUARDRAIL AGGREGATE EROSION CONTROL					
LOCATION			Typical Section	Aggregate Tons	
	STA.	to	STA.		
LT	7915.5		8165.5	4	50.6
LT	8234.23		8429	4	39.4
LT	12283		12463	4	36.4
LT	13302		13387	4	17.2
RT	8001		8165.5	4	33.3
RT	8234.23		8484.23	4	50.6
RT	12228		12478	4	50.6
TOTAL					278.3

78201000 TERMINAL MARKER - DIRECT APPLIED					
63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)					
LOCATION					Qty.
	STA.				EACH
LT	67+29				1
LT	74+42				1
LT	84+29				1
LT	89+68				1
LT	91+58				1
LT	94+80				1
LT	98+18				1
LT	102+14				1
LT	113+49				1
LT	115+02				1
LT	115+55				1
LT	120+46				1
LT	122+83				1
LT	142+37				1
LT	144+32				1
LT	147+97				1
LT	150+24				1
LT	162+33				1
RT	48+54.74				1
RT	50+71				1
RT	55+99				1
RT	64+55				1
RT	65+92				1
RT	80+01				1
RT	86+67				1
RT	89+20				1
RT	90+94				1
RT	94+11				1
RT	97+86				1
RT	101+29				1
RT	109+26				1
RT	113+49				1
RT	142+90				1
RT	157+68				1
RT	161+91				1
TOTAL					35

Earthwork for construction of taper and platform is included in the cost for TRAFFIC BARRIER TERMINAL TY 1, SPECIAL (TANGENT)

78200410 GUARDRAIL MARKERS, TYPE A					
LOCATION					Qty.
	STA.				EACH
TOTAL					35

PLOT DATE = 2/19/2008  
 FILE NAME = S:\GEN\DRFT\STIP\PLANS\GUARD\X0301512\68768-68768.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = boymery

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULES OF QUANTITIES

SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE