

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		TAZEWELL CO. 80%-20% FED-STA Y007			CODE NO	ITEM	UNIT		TAZEWELL CO. 80%-20% FED-STA Y007		
20200100	EARTH EXCAVATION	CU YD	452	452			70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	95.2	95.2			70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
20300100	CHANNEL EXCAVATION	CU YD	52	52			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	46.6	46.6			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
20800150	TRENCH BACKFILL	CU YD	35.6	35.6			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	126.9	126.9			Z0054400	ROCK FILL	CU YD	74	74		
21101615	TOP SOIL FURNISH AND PLACE, 4"	SQ YD	1519	1519			X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	135.8	135.8		
25000210	SEEDING, CLASS 2A	ACRE	0.31	0.31									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27.9	27.9									
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27.9	27.9									
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27.9	27.9									
25100115	MULCH, METHOD 2	ACRE	0.31	0.31									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	62	62									
28000300	TEMPORARY DITCH CHECKS	EACH	18	18									
28000310	AGGRGATE DITCH CHECKS	EACH	1	1									
28000400	PERIMETER EROSION BARRIER	FOOT	392	392									
28100107	STONE RIPRAP, CLASS A4	SQ YD	83	83									
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	127.3	127.3									
28200200	FILTER FABRIC	SQ YD	210.3	210.3									
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	256	256									
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	333.1	333.1									
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1									
50800105	REINFORCEMENT BARS	POUND	17530	17530									
51500100	NAME PLATES	EACH	1	1									
54003000	CONCRETE BOX CULVERTS	CU YD	104.7	104.7									
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	462.5	462.5									
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75									
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4									
63200310	GUARD RAIL REMOVAL	FOOT	200	200									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2									
67100100	MOBILIZATION	L SUM	1	1									

\* SPECIALTY ITEM

FILE NAME c:\projects\198\dillonraek\prof11e.dgn	USER NAME = hudelaorne	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/15/2008	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. RTE. 6758	SECTION 7-BR	COUNTY TAZEWELL	TOTAL SHEETS 21	SHEET NO. 3
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT CONTRACT NO. 68784				