

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	FOOT
RT 576+34.65		RT 577+34.65	100.0
LT 576+75.85		LT 577+25.85	50.0
LT 578+13.35		LT 579+75.85	162.5
RT 578+72.15		RT 579+22.15	50.0
TOTAL =			362.5

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION	FOOT
LT 577+25.85		LT 577+50.85	25.0
RT 577+34.65		RT 577+59.65	25.0
LT 577+88.35		LT 578+13.35	25.0
RT 577+97.15		RT 578+22.15	25.0
TOTAL =			100.0

63000025 STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURE

STATION	TO	STATION	FOOT
LT 577+50.85		LT 577+88.35	37.5
RT 577+59.65		RT 577+97.15	37.5
TOTAL =			75.0

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

STATION	TO	STATION	EACH
RT 575+84.65		RT 576+34.65	1.0
LT 576+25.85		LT 576+75.85	1.0
RT 578+72.15		RT 579+22.15	1.0
LT 579+75.85		LT 580+25.85	1.0
TOTAL =			4.0

66700110 PERMANENT SURVEY MARKERS TO BE ADJUSTED

STATION	O/S	EACH
LT 575+39.9	5.2'	1.0
LT 575+41.5	5.2'	1.0
TOTAL =		2.0

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	FOOT
LT 576+57.1		LT 577+59.1	102.0
RT 576+66.5		RT 577+68.5	102.0
LT 577+79.9		LT 578+81.9	102.0
RT 577+89.5		RT 578+91.5	102.0
TOTAL =			408.0

66600105 FURNISH AND ERECT ROW MARKERS

STATION	O/S	EACH
LT 576+50	40'	1.0
LT 576+50	55'	1.0
RT 576+50	40'	1.0
RT 576+50	55'	1.0
LT 579+00	40'	1.0
LT 579+00	55'	1.0
RT 579+00	40'	1.0
RT 579+00	55'	1.0
TOTAL =		8.0

78201000 TERMINAL MARKER DIRECT APPLIED

STATION	EACH	
RT 575+84.65	1.0	
LT 576+25.85	1.0	
RT 579+22.15	1.0	
LT 580+25.85	1.0	
TOTAL =		4.0

X0323115 REFLECTOR MARKER, TYPE A

STATION	TO	STATION	EACH
RT 576+34.65		RT 578+72.15	4.0
LT 576+75.85		LT 579+75.85	5.0
TOTAL =			9.0

70300100 SHORT-TERM PAVEMENT MARKING

STATION	TO	STATION	LIN.FT.
CL 575+00.00		CL 580+00.00	100.0
*TOTAL =			100.0

* TWO APPLICATIONS (LEVEL BINDER, AND SURFACE)

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

STATION	TO	STATION	SQ. FT.
CL 575+00.00		CL 580+00.00	16.7
TOTAL =			16.7
USE =			17.0

78001110 PAINT PAVEMENT MARKING-LINE 4" (WHITE)

STATION	TO	STATION	LIN.FT.
LT 575+00.00		LT 580+00.00	500.0
RT 575+00.00		RT 580+00.00	500.0
SUBTOTAL =			1000.0

78001110 PAINT PAVEMENT MARKING-LINE 4" (YELLOW)

STATION	TO	STATION	LIN.FT.
CL 575+00.00		CL 580+00.00	166.7
SUBTOTAL =			166.7
USE =			1167.0

78100100 RAISED REFLECTIVE MARKER (AMBER BIDIRECTIONAL)

STATION	TO	STATION	EACH
575+00 (80' CTS.)		580+00	6.0
TOTAL =			6.0

78300200 RAISED REFLECTIVE MARKER REMOVAL

STATION	TO	STATION	EACH
575+00		580+00	6.0
TOTAL =			6.0