

EARTHWORK

STATION	TO STATION	EARTH EXCAVATION (CUT) CU YD	EARTH EXCAVATION (SHRINKAGE) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD
68+08.21	74+00.00	35	26	133	-107
TOTAL		35	26	133	-107

EARTH EXCAVATION: 35 CY  
FURNISHED EXCAVATION: 107 CY

SEEDING, FERTILIZERS AND MULCH

STATION	TO STATION	SEEDING, CLASS 2A (ACRE)	NITROGEN (POUND)	PHOSPHOROUS (POUND)	POTASSIUM (POUND)	TEMPORARY EROSION CONTROL SEEDING (POUND)
68+08.21	70+91.83	0.25	22.5	22.5	22.5	25
71+85.17	74+00.00	0.25	22.5	22.5	22.5	25
TOTAL		0.5	45	45	45	50

EROSION CONTROL BLANKET

STATION	TO STATION	SQ YD
68+08.21	70+91.83	859
71+85.17	74+00.00	787
TOTAL		1,646

AGGREGATE DITCH CHECK

STATION	OFFSET	EACH
69+78.71	LT 28.06	1
70+76.65	LT 26.56	1
72+00.22	LT 25.95	1
69+42.96	RT 32.84	1
70+64.80	RT 28.54	1
72+11.08	RT 29.38	1
TOTAL		6

PERIMETER EROSION BARRIER

STATION	TO STATION	OFFSET	FOOT
69+00.00	70+92.50	LT	193
68+05.00	70+92.50	RT	288
71+84.50	74+62.73	LT	279
71+84.50	74+00.00	RT	216
TOTAL			976

BITUMINOUS MATERIALS (PRIME COAT)

STATION	TO STATION	GALLONS
70+62.50	72+14.50	38
TOTAL		38

HOT-MIX ASPHALT SURFACE REMOVAL - 1 1/2"

STATION	TO STATION	SQ YD
70+62.50	70+92.50	87
71+84.50	72+14.50	87
TOTAL		174

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

STATION	TO STATION	TONS
70+62.50	72+14.50	54
TOTAL		54

PIPE CULVERT REMOVAL

STATION	TO STATION	OFFSET	FEET
72+68.15	73+26.29	LT 11.81	59
72+33.23	72+88.96	RT 15.63	56
TOTAL			115

SHORT-TERM PAVEMENT MARKING

STATION	TO STATION	RIGHT (WHITE)	CENTER (YELLOW)	LEFT (WHITE)	TOTAL
70+62.50	72+14.50	0	16	0	16


WORK ZONE PAVEMENT MARKING REMOVAL

STATION	TO STATION	SQ FT
70+62.50	72+14.50	6
TOTAL		6

PAINT PAVEMENT MARKING - LINE 4"

STATION	TO STATION	RIGHT (WHITE)	CENTER (YELLOW)	LEFT (WHITE)	TOTAL
70+62.50	72+14.50	152	40	152	344

FILE NAME = c:\projects\4506704 (8/1/2008)02.21 final submittal\mrcostation files\schedule of quantities.dgn



USER NAME = collierbw	DESIGNED - RRD	REVISED -
PLOT SCALE =	DRAWN - KAS	REVISED -
PLOT DATE = 3/24/2008	CHECKED - JAR	REVISED -
	DATE - 3/14/08	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
502	(86BR)BR	CHAMPAIGN	30	6
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				CONTRACT NO. 70426