

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(20-1)RS-2	DEWITT	97	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULES OF QUANTITIES

LANDSCAPING SCHEDULE

STATION	TO	STATION	AREA (ACRE)	28000250 TEMPORARY EROSION SEEDING (POUND)	25000350 SEEDING CLASS 7 (ACRE)	25000210 SEEDING CLASS 2A (ACRE)	25000400 NITROGEN FERT. (POUNDS)	25000500 PHOS. FERT. (POUNDS)	25000600 POTAS. FERT. (POUNDS)	25100115 MULCH METHOD 2 (ACRE)	
<u>IMPACT ATTENUATORS</u>											
636+45		639+36	0.4	40.0	0.4	0.4	36.0	36.0	36.0	0.4	
843+90		850+00	0.80	80.0	0.8	0.8	72.0	72.0	72.0	0.8	
<u>GUARDRAIL TERMINALS</u>											
<u>SN 020-0026</u>											
EASTBOUND	RT	742+88.85									
EASTBOUND	LT	741+86.35									
EASTBOUND	RT	743+38.85	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
EASTBOUND	LT	742+36.35	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0027</u>											
WESTBOUND	LT	779+17.65	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
WESTBOUND	RT	751+78.65	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0028</u>											
EASTBOUND	RT	772+05.85	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
EASTBOUND	LT	771+38.35	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0029</u>											
WESTBOUND	LT	812+01.65	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
WESTBOUND	RT	779+17.65	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0030</u>											
EASTBOUND	RT	789+44.85	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
EASTBOUND	LT	803+62.35	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0031</u>											
WESTBOUND	RT	812+01.65	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0032</u>											
EASTBOUND	LT	812+37.35	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0033</u>											
WESTBOUND	LT	870+41.45	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
WESTBOUND	RT	820+84.65	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0036</u>											
EASTBOUND	RT	862+44.55	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
EASTBOUND	LT	861+82.05	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
<u>SN 020-0037</u>											
WESTBOUND	RT	870+41.45	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
WESTBOUND	LT	869+78.95	0.03	3.0	0.03	0.03	2.7	2.7	2.7	0.03	
TOTAL =				1.74	174.0	1.74	1.74	156.60	156.60	156.60	1.74
USE =				2.0	174.0	2.0	2.0	157.0	157.0	157.0	2.0

EROSION CONTROL SCHEDULE

STATION	28000300 TEMPORARY DITCH CHECKS (EACH)	28000500 INLET&PIPE PROTECTION (EACH)
636+16		1.0
636+32.64	1.0	
637+32.64	1.0	
639+60		1.0
640+68.58	1.0	
841+00		1.0
843+82.49	1.0	
844+82.49	1.0	
847+63.67	1.0	
848+63.67	1.0	
851+00		1.0
TOTAL =		7.0
		4.0

PLOT DATE = 3/28/2008
 FILE NAME = c:\projects\05022805 (v8)\70475cover.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (20-1)RS-2
 DEWITT COUNTY

SCALE: N/A
 DATE: 02-25-08

DRAWN BY: CADD
 CHECKED BY: