

SCHEDULES OF QUANTITIES

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|------------|------------------|--------------|-----------|
| 74 | (20-1)RS-2 | DEWITT | 97 | 20 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

48203100 HOT-MIX ASPHALT SHOULDERS (CONT'D)

| | STATION | TO | STATION | LENGTH (FOOT) | WIDTH (FOOT) | AREA (SQ YD) | SHOULDER THICKNESS (INCHES) | 48203100 HMA SHLD (TON) | 40600100 BIT MATLS PR CT (GAL) | 40600300 AGG PR CT (TONS) | |
|-------------------------------------|--------------|----|--------------|------------------|-----------------|-----------------|-----------------------------------|-------------------------------|---|---------------------------------|-------|
| <u>INTERCHANGE RAMP</u> | | | | | | | | | | | |
| RAMP A | WB 106+62.40 | | WB 121+84.37 | 1521.97 | 8 | 1352.9 | 2.25 | 170.5 | 135.3 | 2.7 | |
| RAMP A | WB 106+63.40 | | WB 121+85.37 | 1521.97 | 4 | 676.4 | 2.25 | 85.2 | 67.6 | 1.4 | |
| RAMP B | WB 200+24.84 | | WB 208+45.36 | 820.52 | 8 | 729.4 | 2.25 | 91.9 | 72.9 | 1.5 | |
| RAMP B | WB 200+25.84 | | WB 208+46.36 | 820.52 | 4 | 364.7 | 2.25 | 45.9 | 36.5 | 0.7 | |
| RAMP C | EB 306+62.40 | | EB 330+55.90 | 2393.50 | 8 | 2127.6 | 2.25 | 268.1 | 212.8 | 4.3 | |
| RAMP C | EB 306+63.40 | | EB 330+56.90 | 2393.50 | 4 | 1063.8 | 2.25 | 134.0 | 106.4 | 2.1 | |
| RAMP D | EB 400+24.84 | | EB 412+06.53 | 1181.69 | 8 | 1050.4 | 2.25 | 132.3 | 105.0 | 2.1 | |
| RAMP D | EB 400+25.84 | | EB 412+07.53 | 1181.69 | 4 | 525.2 | 2.25 | 66.2 | 52.5 | 1.1 | |
| | | | | | | | | SUB-TOTAL = | 994.2 | 789.0 | 15.8 |
| <u>WIDENING AT INTERCHANGE RAMP</u> | | | | | | | | | | | |
| RAMP A | WB 106+62.40 | | WB 121+84.37 | 1521.97 | 2 | 338.2 | 10.25 | 194.1 | 33.8 | 0.7 | |
| RAMP B | WB 200+24.84 | | WB 208+45.36 | 820.52 | 2 | 182.3 | 10.25 | 104.7 | 18.2 | 0.4 | |
| RAMP C | EB 306+62.40 | | EB 330+55.90 | 2393.50 | 2 | 531.9 | 10.25 | 305.3 | 53.2 | 1.1 | |
| RAMP D | EB 400+24.84 | | EB 412+06.53 | 1181.69 | 2 | 262.6 | 10.25 | 150.7 | 26.3 | 0.5 | |
| | | | | | | | | SUB-TOTAL = | 754.8 | 131.5 | 2.6 |
| <u>GORE AREAS</u> | | | | | | | | | | | |
| REST AREA | EB 658+65.00 | | EB 662+33.70 | - | VAR | 421.1 | 1.5 | 35.4 | 42.1 | 0.8 | |
| REST AREA | WB 674+82.00 | | WB 679+10.15 | - | VAR | 331.1 | 1.5 | 27.8 | 33.1 | 0.7 | |
| REST AREA | EB 694+54.78 | | EB 698+85.00 | - | VAR | 331.1 | 1.5 | 27.8 | 33.1 | 0.7 | |
| REST AREA | WB 711+31.23 | | WB 715+00.00 | - | VAR | 420.0 | 1.5 | 35.3 | 42.0 | 0.8 | |
| RAMP B | WB 832+40.00 | | WB 835+74.53 | - | VAR | 243.8 | 1.5 | 20.5 | 24.4 | 0.5 | |
| RAMP C | EB 832+65.00 | | EB 836+25.23 | - | VAR | 419.1 | 1.5 | 35.2 | 41.9 | 0.8 | |
| RAMP A | WB 856+24.80 | | WB 860+05.00 | - | VAR | 459.4 | 1.5 | 38.6 | 45.9 | 0.9 | |
| RAMP D | EB 857+10.70 | | EB 860+53.00 | - | VAR | 247.7 | 1.5 | 20.8 | 24.8 | 0.5 | |
| | | | | | | | | SUB-TOTAL = | 241.4 | 287.3 | 5.7 |
| | | | | | | | | TOTAL = | 10,129.2 | 10,897.0 | 217.9 |
| | | | | | | | | USE = | 10,129.0 | 10,897.0 | 218.0 |

PLOT DATE = 3/28/2008
 FILE NAME = c:\projects\4592295 (v8)\70475cover.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (20-1)RS-2
 DEWITT COUNTY

SCALE: N/A
 DATE: 02-25-08
 DRAWN BY: CADD
 CHECKED BY: