

| F.A.I. RTE.         | SECTION    | COUNTY           | TOTAL SHEETS | SHEET NO. |
|---------------------|------------|------------------|--------------|-----------|
| 74                  | (20-1)RS-2 | DEWITT           | 97           | 27        |
| STA.                |            | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS   | FED. AID PROJECT |              |           |

# SCHEDULES OF QUANTITIES

## 78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" (WHITE)

| STATION           | TO | STATION           | FOOT     |
|-------------------|----|-------------------|----------|
| EB 608+76.00      |    | EB 610+00.00 (BK) | 124.0    |
| WB 608+90.00      |    | WB 610+00.00 (BK) | 110.0    |
| EB 633+68.77 (AH) |    | EB 655+70.00      | 2,201.2  |
| WB 633+68.77 (AH) |    | WB 666+29.87      | 3,261.1  |
| EB 655+70.00      |    | EB 659+74.37      | 404.4    |
| EB 655+70.00      |    | EB 662+33.70      | 663.7    |
| WB 666+29.87      |    | WB 675+79.87      | 950.0    |
| WB 666+29.87      |    | WB 679+10.15      | 1,280.3  |
| EB 659+74.37      |    | EB 662+33.70      | 259.3    |
| WB 675+79.87      |    | WB 679+10.15      | 330.3    |
| EB 662+33.70      |    | EB 694+54.78      | 3,221.1  |
| WB 679+10.15      |    | WB 711+31.23      | 3,221.1  |
| WB 711+31.23      |    | WB 717+94.93      | 663.7    |
| EB 694+54.78      |    | EB 697+85.06      | 330.3    |
| EB 694+54.78      |    | EB 707+35.06      | 1,280.3  |
| WB 711+31.23      |    | WB 713+90.56      | 259.3    |
| EB 697+85.06      |    | EB 707+35.06      | 950.0    |
| WB 713+90.56      |    | WB 717+94.93      | 404.4    |
| EB 707+35.06      |    | EB 909+40.50      | 20,205.4 |
| EB 829+63.00      |    | EB 836+25.23      | 662.2    |
| EB 857+10.70      |    | EB 864+93.00      | 782.3    |
| WB 717+94.93      |    | WB 910+00.00      | 19,205.1 |
| WB 824+85.00      |    | WB 835+74.53      | 1,089.5  |
| WB 856+24.80      |    | WB 863+06.00      | 681.2    |

SUB-TOTAL = 62,540.2

### INTERCHANGE RAMPS

|        |              |              |         |
|--------|--------------|--------------|---------|
| RAMP A | WB 106+62.40 | WB 121+84.37 | 1,522.0 |
| RAMP B | WB 200+24.84 | WB 208+45.36 | 820.5   |
| RAMP C | EB 306+62.40 | EB 330+55.90 | 2,393.5 |
| RAMP D | EB 400+24.84 | EB 412+06.53 | 1,181.7 |

SUB-TOTAL = 5,917.7

TOTAL = 68,457.9

USE = 68,458.0

## 78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW)

| STATION           | TO | STATION           | FOOT     |
|-------------------|----|-------------------|----------|
| EB 608+76.00      |    | EB 610+00.00 (BK) | 124.0    |
| WB 608+90.00      |    | WB 610+00.00 (BK) | 110.0    |
| EB 633+68.77 (AH) |    | EB 655+70.00      | 2,201.2  |
| WB 633+68.77 (AH) |    | WB 666+29.87      | 3,261.1  |
| EB 655+70.00      |    | EB 659+74.37      | 404.4    |
| WB 666+29.87      |    | WB 675+79.87      | 950.0    |
| EB 659+74.37      |    | EB 662+33.70      | 259.3    |
| WB 675+79.87      |    | WB 679+10.15      | 330.3    |
| EB 662+33.70      |    | EB 694+54.78      | 3,221.1  |
| WB 679+10.15      |    | WB 711+31.23      | 3,221.1  |
| EB 694+54.78      |    | EB 707+35.06      | 1,280.3  |
| WB 711+31.23      |    | WB 717+94.93      | 663.7    |
| EB 707+35.06      |    | EB 909+40.50      | 20,205.4 |
| WB 717+94.93      |    | WB 910+00.00      | 19,205.1 |

SUB-TOTAL = 55,437.0

### INTERCHANGE RAMPS

|        |              |              |         |
|--------|--------------|--------------|---------|
| RAMP A | WB 106+62.40 | WB 121+84.37 | 1,522.0 |
| RAMP B | WB 200+24.84 | WB 208+45.36 | 820.5   |
| RAMP C | EB 306+62.40 | EB 330+55.90 | 2,393.5 |
| RAMP D | EB 400+24.84 | EB 412+06.53 | 1,181.7 |

SUB-TOTAL = 5,917.7

TOTAL = 61,354.6

USE = 61,355.0

TOTAL QUANTITY = 129,813.0

## 78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8" (WHITE)

| STATION    | TO           | STATION      | FOOT  |
|------------|--------------|--------------|-------|
| GORE AREAS |              |              |       |
| REST AREA  | EB 658+65    | EB 662+33.70 | 738.0 |
| REST AREA  | WB 674+82    | WB 679+10.15 | 860.0 |
| REST AREA  | EB 694+54.78 | EB 698+85    | 860.0 |
| REST AREA  | WB 711+31.23 | WB 715+00    | 738.0 |
| RAMP A     | WB 832+40    | WB 835+74.53 | 670.0 |
| RAMP B     | EB 832+65    | EB 836+25.23 | 720.0 |
| RAMP C     | WB 856+24.80 | WB 860+05    | 760.0 |
| RAMP D     | EB 857+10.70 | EB 860+53    | 685.0 |

TOTAL = 6,031.0

PLOT DATE = 3/28/2008  
 FILE NAME = c:\projects\4582285 (8)\70475cover.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES OF QUANTITIES**  
 F.A.I. ROUTE 74  
 SECTION (20-1)RS-2  
 DEWITT COUNTY

SCALE: N/A  
 DATE: 02-25-08  
 DRAWN BY: CADD  
 CHECKED BY: