SCHEDULE OF QUANTITIES

SIDEWALK PAY ITEMS

STATION	CURB REMOVAL (FOOT) (44003300)	RAMP TYPE	DETECTABLE WARNINGS SQ FT (X0324872)	PCC SIDEWALK, 4" SQFT (42400100)
299+36	17	B	34	
				645.00
300+65		A	12	
301+10		A	12	
				830.00
302+76	6	A	12	
303+00	6	A	12	
				840.00
304+68	6	A	12	
305+05	6	A	12	
				640.00
306+33	6	A	12	
306+47	6	A		
				1150.00
308+77	6	A	12	
309+06	6	A	12	
				1915.00
312+89	6	A	12	
313+16	6	A	12	
				2170.00
317+50	6	A	12	
317+75	6	A	12	
				1115.00
319+98	6	A	12	
TOTAL	**95**		**202**	**9305**

TEMPORARY RAMP (40600990)

@B.O.J. (SB)	13.33	SQ YDS
@LAFAYETTE STREET	13.33	SQ YDS
@ARMORY DRIVE	13.33	SQ YDS
@B.O.J. (NB)	13.33	SQ YDS
@E.O.J. (NB & SB)	26.60	SQ YDS
TOTAL	**79.93**	**SQ YDS**
USE	**80.0**	**SQ YDS**

PARTIAL DEPTH PATCHING

STATION	LANE DIR	LENGTH	WIDTH	AREA SQ YD	POUNDS/ SQYD	DEPTH (INCHES)	POUND/ TON	TONS
305+90	NB	6	12	8.00	112	3	2000	1.34
307+85	NB	6	12	8.00	112	3	2000	1.34
310+50	NB	6	12	8.00	112	3	2000	1.34
265+00	SB	6	12	8.00	112	3	2000	1.34
264+00	SB	6	12	8.00	112	3	2000	1.34
262+00	SB	6	12	8.00	112	3	2000	1.34
261+00	SB	6	12	8.00	112	3	2000	1.34
258+50	SB	6	12	8.00	112	3	2000	1.34
257+50	SB	6	12	8.00	112	3	2000	1.34
TOTAL				72.00				12.10
							USE	13.0

FILE NAME = c:\projects\d503606 (v8)\70516-text.dgn	USER NAME = collierbw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/24/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
730	(56)RS-2	MCLEAN	51	10
		CONTRACT NO. 70516		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		