

70682

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	LOCATION OF WORK:	
					URBAN FAP 730 U.S. 51 BR (CENTER ST.) & LOCUST ST. 100% STATE	URBAN FAP 730 U.S. 51 BR (MAIN ST.) & LOCUST ST. 100% STATE
					Y031-1F	Y031-1F
					QUANTITY	QUANTITY
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		SQ FT	114.0	63.0	51.0
44000600	SIDEWALK REMOVAL		SQ FT	162.0	92.0	70.0
44002020	CONCRETE MEDIAN SURFACE REMOVAL		SQ FT	34.0	34.0	
44002805	ISLAND REMOVAL		SQ FT	60.0		60.0
60618300	CONCRETE MEDIAN SURFACE, 4 INCH		SQ FT	38.0	38.0	
67100100	MOBILIZATION		L SUM	1.0	.5	.5
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701		L SUM	1.0	.5	.5
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801		L SUM	1.0	.5	.5
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)		EACH	2.0	1.0	1.0
81012600	CONDUIT IN TRENCH, 2" DIA., PVC		FOOT	54.0	22.0	32.0
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC		FOOT	38.0	32.0	6.0
81013100	CONDUIT IN TRENCH, 5" DIA., PVC		FOOT	15.0	8.0	7.0
81021550	CONDUIT, AUGERED 2" DIA., PVC		FOOT	140.0	86.0	54.0
81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC		FOOT	36.0	36.0	
81021570	CONDUIT, AUGERED 3" DIA., PVC		FOOT	373.0	130.0	243.0
81021590	CONDUIT, AUGERED 4" DIA., PVC		FOOT	45.0	45.0	
81030100	CONDUIT SPLICE		EACH	2.0	1.0	1.0
81400100	HANDHOLE		EACH	9.0	5.0	4.0
81400300	DOUBLE HANDHOLE		EACH	2.0	1.0	1.0
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	92.0	62.0	30.0
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET		EACH	2.0	1.0	1.0
85900100	TRANSCEIVER		EACH	2.0	1.0	1.0
87301235	ELECTRIC CABLE IN CONDUIT, SIGNALNO. 14 4C		FOOT	885.0	370.0	515.0
87301245	ELECTRIC CABLE IN CONDUIT, SIGNALNO. 14 5C		FOOT	1,670.0	710.0	960.0
87301255	ELECTRIC CABLE IN CONDUIT, SIGNALNO. 14 7C		FOOT	860.0	402.0	458.0

FILE NAME =	USER NAME = collierbw	DESIGNED - RDB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\projects\0506207 (v0)\locust.street.dgn		DRAWN - RDB	REVISED -		730	(61,62)TS	MCLEAN	13	3	
PLOT SCALE = 40,0000' / IN.		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
PLOT DATE = 3/20/2008		DATE -	REVISED -		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT CONTRACT NO. 70682					