

SUMMARY OF QUANTITIES (cont.)

			TOTAL	URBAN Y031-1F	URBAN Y031-1F
87301705	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 3 PAIR	FOOT	1,736.0	371.0	1,365.0
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	7.0	4.0	3.0
87502460	TRAFFIC SIGNAL POST, GALVANIZED STEEL 12 FT.	EACH	1.0	1.0	
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2.0	2.0	
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1.0		1.0
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1.0	1.0	
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1.0		1.0
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24.8	15.5	9.3
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7.0	3.5	3.5
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	13.5	13.5	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	37.0	13.0	24.0
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2.0	1.0	1.0
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7.0	1.0	6.0
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	1.0		1.0
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	3.0		3.0
88102850	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, BRACKET MOUNTED	EACH	1.0		1.0
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	6.0		6.0
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	5.0	5.0	
89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	10.0	10.0	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,380.0	353.0	2,027.0
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	179.0	124.0	55.0
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2.0	1.0	1.0
89502380	REMOVE EXISTING HANDHOLE	EACH	6.0	3.0	3.0
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	11.0	6.0	5.0
X0703200	CONCRETE ISLAND (SPECIAL)	SQ FT	56.0		56.0
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	801.0	414.0	387.0

FILE NAME =	USER NAME = collierbv	DESIGNED - RDB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\projects\0506207 (w8)\locust_street.dgn		DRAWN - RDB	REVISED -		730	(61,62)TS	MCLEAN	13	4
PLOT SCALE = 40,0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 70682				
PLOT DATE = 3/20/2008		DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT