

SCHEDULE OF QUANTITIES - MAIN ST. & LOCUST ST.

CONCRETE FOUNDATION TY A

LOCATION	FOOT
Sta. 42+33.9; 35.0' Rt.	3.1
Sta. 42+42.5; 26.2' Lt.	3.1
Sta. 42+93.4; 26.0' Rt.	3.1
Total =	9.3 FOOT

CONCRETE FOUNDATION TY E .36"

LOCATION	FOOT
Sta. 43+02.7; 36.7' Lt.	13.0
Sta. 43+52.4; 26.6' Rt.	11.0
Total =	24.0 FOOT

HANDHOLES

LOCATION	EACH
Sta. 42+36.5; 29.3' Lt.	1
Sta. 42+91.3; 23.4' Lt.	1
Sta. 43+03.0; 40.1' Rt.	1
Sta. 43+49.4; 25.2' Rt.	1
Total =	4 EACH

TRAFFIC SIGNAL POST GALVS. 10

LOCATION	EACH
Sta. 42+33.9; 35.0' Lt.	1
Sta. 42+42.5; 26.2' Lt.	1
Sta. 42+93.4; 26.0' Rt.	1
Total =	3 EACH

DOUBLE HANDHOLE

LOCATION	EACH
Sta. 42+27.0; 29.4' Lt.	1

SIDEWALK REMOVAL

LOCATION	SQ. FT.
NW QUAD	50
NE QUAD	15
SE QUAD	5
Total =	70 SQ. FT.

ISLAND REMOVAL

LOCATION	SQ. FT.
SE CORNER ISLAND	60

PCC CONC SIDEWALK 5

LOCATION	SQ. FT.
NW QUAD	33
NE QUAD	12
SE QUAD	2
SW QUAD	4
Total =	51 SQ. FT.

CONCRETE ISLAND SPECIAL

LOCATION	SQ. FT.
SE CORNER ISLAND	56

REMOVE EXIST HANDHOLE

LOCATION	EACH
Sta. 42+36.5; 29.3' Rt.	1
Sta. 43+11.5; 20.6' Rt.	1
Sta. 43+63.2; 23.8' rt.	1
Total =	3 EACH

REMOVE EXIST CONC FDN

LOCATION	EACH
Sta. 42+40.9; 37.3' Lt	1
Sta. 42+41.7; 35.9' Rt.	1
Sta. 42+94.3; 21.6' Rt.	1
Sta. 42+99.3; 34.7' Lt.	1
Sta. 43+11.6; 20.1' Lt.	1
Total =	5 EACH