

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10,92-8 HB-1)BR	CHAMPAIGN	93	8
STA. TO STA.		ILLINOIS FED. AID PROJECT		
FED. ROAD DIST. NO. -		CONTRACT NO. 70695		

HOT-MIX ASPHALT PAVEMENT

LOCATION	HOT-MIX ASPHALT MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SHOULDERS 6 1/2"	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N30	HOT-MIX ASPHALT SURFACE COURSE MIX D, N50	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N50	HOT-MIX ASPHALT BINDER COURSE IL-19.0L N30	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX E, N105	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE IL-19.0, N105
STATION TO STATION	GAL.	SO. YD.	TON	TON	TON	TON	TON	TON	TON
IL 49S									
306+23.50 TO 307+30.00	12.7	74.9		9.3	32.8				
307+30.00 TO 307+72.66 LT	6.3	37.9		3.2	4.4	7.9			
307+30.00 TO 41+15.00 RT	9.5	20.8		1.8	6.4	12.8			
307+72.66 TO 42+90.00 LT	47.6	14.3		1.5	20.0	47.9	237.1		
41+15.00 TO 42+90.00 RT	44.4	53.4		4.5	18.0	43.0	231.1		
42+90.00 TO 48+54.50	187.3	1127.5		94.7	115.9	277.5			
51+45.50 TO 57+10.00	187.3	1127.5		94.7	115.9	277.5			
57+10.00 TO 58+84.00 LT	44.4	51.2		4.3	17.9	42.8	252.8		
57+10.00 TO 326+00.00 RT	50.8	30.9		2.2	21.6	51.7	260.3		
58+84.00 TO 326+21.50 LT	9.5	19.2		1.6	5.9	13.2			
326+00.00 TO 326+21.50 RT	3.2	7.2		0.6	2.2	4.3			
326+21.50 TO 326+81.50	9.5	40.0		6.0	18.5				
I-74									
2294+00.00 TO 1003+85.00 WB	203.2		174.8	94.1				161.3	299.6
2294+00.00 TO 1003+85.00 EB	203.2		174.8	94.1				161.3	299.6
RAMP A									
401+00.00 TO 401+65.00	9.5		16.8	13.3	15.5				
401+65.00 TO 402+10.00	9.5			5.0	5.9	13.6			
402+10.00 TO 403+14.26	101.6				45.2	110.2	403.5		
RAMP B									
298+41.29 TO STA. 299+58.00	101.6				45.0	105.1	383.0		
299+58.00 TO 300+15.00	12.7		24.6	6.8	8.0	15.2			
300+15.00 TO 300+75.00	9.5			13.8	16.1				
RAMP C									
501+00.00 TO 501+60.00	9.5			13.0	15.2				
501+60.00 TO 502+11.00	12.7		22.0	6.1	7.2	9.86			
502+11.00 TO 503+21.57	95.2				42.7	100.2	340.9		
RAMP D									
98+50.99 TO 99+35.53	101.6		27.6		44.1	106.8	413.4		
99+35.53 TO 100+09.50	15.9			8.2	9.7	19.3			
100+09.50 TO 100+75.00	9.5			13.3	15.6				
ACTUAL TOTAL	1,507.7	2,604.8	440.6	492.1	649.7	1,258.9	2,522.3	322.6	599.2
USED TOTAL	1,508.0	2,605.0	441.0	493.0	650.0	1,259.0	2,523.0	323.0	600.0

AGGREGATE

LOCATION	AGGREGATE (PRIME COAT)	AGGREGATE SHOULDERS TYPE B
STATION TO STATION	TON	TON
IL 49 S		
306+42.61 LT (P.E.)	0.1	
306+63.25 RT (F.E.)		
42+90.00 TO 48+60.50	1.4	
51+39.50 TO 57+10.00	1.4	
IL 49S		
306+23.5 TO 307+30.00 LT		7.7
306+87.00 TO 41+15.00 RT		17.1
58+84.00 TO 326+81.50 LT		19.6
326+00.00 TO 326+81.50 RT		14.4
RAMP A		
401+00.00 TO 402+10.00		14.7
RAMP B		
299+58.00 TO 300+75.00		10.3
RAMP C		
501+00.00 TO 502+11.00		14.8
RAMP D		
99+35.53 TO 100+75.00		18.6
I-74		
2294+00.00 TO 1003+85.00 WB		51.5
2294+00.00 TO 1003+85.00 EB		51.5
ACTUAL TOTAL	2.9	220.2
USED TOTAL	3.0	221.0

GRANULAR EMBANKMENT SPECIAL

STATION	(CU. YD.)
42+90 TO 43+00	21.1
43+00 TO 43+50	122.1
43+50 TO 44+00	151.0
44+00 TO 44+50	170.5
44+50 TO 45+00	173.4
45+00 TO 45+50	179.9
45+50 TO 46+00	185.5
46+00 TO 46+50	192.4
46+50 TO 46+76.5	98.7
46+76.5 TO 47+00	74.5
47+00 TO 47+50	138.5
47+50 TO 48+00	123.1
48+00 TO 48+60.5	135.8
51+39.5 TO 52+00	133.8
52+00 TO 52+50	115.2
52+50 TO 53+00	126.3
53+00 TO 53+23.5	64.5
53+23.5 TO 53+50	76.0
53+50 TO 54+00	148.8
54+00 TO 54+50	159.4
54+50 TO 55+00	168.2
55+00 TO 55+50	177.1
55+50 TO 56+00	178.8
56+00 TO 56+50	160.6
56+50 TO 56+96	116.4
56+96 TO 57+10	29.0
ACTUAL TOTAL	3,420.6
USED TOTAL	3,421.0

BRIDGE APPROACH

LOCATION	BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT	PAVEMENT GROOVING
STATION TO STATION	SO. YD.	SO. YD.	SO. YD.
IL 49 S			200
48+60.5 TO 48+90.5	135.5	139.0	
51+09.5 TO 51+39.5	135.5	139.0	
ACTUAL TOTAL	271.0	278.0	254.0
USED TOTAL	271.0	278.0	254.0

TEMPORARY RAMP

STATION	LOCATION	AREA (SO YD)
2294+00.0	I-74 EB&WB	281.2
1003+85.0	I-74 EB&WB	281.2
306+23.5	IL 49	12.2
326+81.5	IL 49	12.2
401+00.0	RAMP A	14.4
300+75.0	RAMP B	15.6
501+00.0	RAMP C	15.6
100+75.0	RAMP D	14.4
ACTUAL TOTAL		646.8
USED TOTAL		647.0

CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)

STATION	SO. FT.
RAMP D	70.4
RAMP A	104.3
ACTUAL TOTAL	174.7
USED TOTAL	175.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 06/2003

DRAWN BY: FML
CHECKED BY: YML