

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10,92-8 HB-1)BR	CHAMPAIGN	93	10
STA. TO STA.		ILLINOIS FED. AID PROJECT		
FED. ROAD DIST. NO. -		CONTRACT NO. 70695		

GUARDRAIL

LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE B	TRAFFIC BARRIER TERMINAL	
		TYPE 6	TYPE 1, SPECIAL (TANGENT)
STATION TO STATION	FOOT	EACH	EACH
43+47.35 TO 48+47.35, LT	500.0		
43+22.35 TO 48+47.35, RT	525.0		
51+52.65 TO 56+77.65, LT	525.0		
51+52.65 TO 56+52.65, RT	500.0		
48+47.35 TO 48+93.00, LT		1	
48+47.35 TO 48+93.00, RT		1	
51+07.00 TO 51+52.65, LT		1	
51+07.00 TO 51+52.65, RT		1	
42+97.35 TO 43+47.35, LT			1
42+72.35 TO 43+22.35, RT			1
56+77.65 TO 57+27.65, LT			1
56+52.65 TO 57+02.65, RT			1
ACTUAL TOTAL	2,050.0	4	4
USED TOTAL	2,050.0	4	4

WORK ZONE PAVEMENT MARKINGS

LOCATION	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	FOOT	SO. FT.
IL 49 S			1,928.2
306+23.5 TO 326+81.5		163.9	
306+23.5 TO 43+00.0 & 51+00.0 TO 326+81.5		298.0	
41+50.0 TO 43+00.0 & 57+00.0 TO 58+48.0		2,242.0	
43+00 TO 57+00		2,993.4	
306+23.5 TO 326+81.5			
306+23.5 TO 42+90.0	48.4		
57+10.0 TO 326+81.5	39.0		
RAMP A	95.5	712.4	269.3
RAMP B	33.1	490.4	174.5
RAMP C	31.0	431.4	154.1
RAMP D	98.0	746.5	281.5
I-74			
2294+00 TO 1003+85 (WB)	111.1	1,389.0	500.0
2294+00 TO 1003+85 (EB)	111.1	1,389.0	500.0
ACTUAL TOTAL	567.2	10,856.0	3,807.6
USED TOTAL	568.0	10,856.0	3,808.0

SHOULDER RUMBLE STRIP

STATION TO STATION	FOOT
I-74	
2294+00 TO 1003+85 (WB)	1234.7
2294+00 TO 1003+85 (EB)	1234.7
ACTUAL TOTAL	2,469.4
USED TOTAL	2,470.0

GUARDRAIL MARKERS

LOCATION	GUARDRAIL MARKERS TYPE A	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	TERMINAL MARKER - DIRECT APPLIED
	EACH	EACH	EACH
43+50 RT	1		
44+30	2		
45+10 RT	1		
45+90	2		
46+70 RT	1		
47+50	2		
52+50	2		
53+30 LT	1		
54+10	2		
54+90 LT	1		
55+70	2		
56+50 LT	1		
48+95		2	
49+65		2	
50+35		2	
51+05		2	
42+78.6 RT			1
42+97.3 LT			1
56+96.4 RT			1
57+21.4 LT			1
ACTUAL TOTAL	18	8	4
USED TOTAL	18	8	4

PAVEMENT MARKINGS

LOCATION	THERMOPLASTIC PAVEMENT MARKING			EPOXY P.M. LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER
	LINE 4"	LINE 12"	LINE 24"		
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	EACH
IL 49 S					
306+23.5 TO 43+00.0 & 51+00.0 TO 326+81.5	163.9				
41+50.0 TO 43+00.0 & 57+00.0 TO 58+48.0	298.0				
43+00 TO 57+00	2,242.0				
306+23.5 TO 326+81.5	2,993.4				
48+60.5 TO 51+39.5				1,116.0	
RAMP A	712.2	250.4	36.0		
RAMP B	490.2				16
RAMP C	431.4				16
RAMP D	746.5	262.8	36.0		
I-74					
2294+00 TO 1003+85 (WB)	1,389.2				
2294+00 TO 1003+85 (EB)	1,389.2				
ACTUAL TOTAL	10,857.0	513.2	72.0	1,116.0	32
USED TOTAL	10,857.0	514.0	72.0	1,116.0	32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 06/2003

DRAWN BY: FML
CHECKED BY: YML