

## GENERAL NOTES

**G.N.-100**

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

**G.N.-442B -- PATCHING SCHEDULES**

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF THE FULL-DEPTH PATCHES MAY OCCUR.

**G.N. -780 SPECIAL**

PAINT PAVEMENT MARKINGS SHALL BE APPLIED UPON COMPLETION OF THE PATCH WORK. PAINT PAVEMENT MARKINGS SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS.

**G.N.-781**

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

**G.N.-1004.01**

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

**NO COMMITMENTS**

FILE NAME = c:\projects\0578783\78783plans.dgn	USER NAME = collierbw	DESIGNED - RTB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.J. RTE. 74	SECTION 110-92-8,92-911	COUNTY •	TOTAL SHEETS 13	SHEET NO. 5
PLOT SCALE = 100.0000' / IN.	DRAWN - JRP 12-14-07	CHECKED -	REVISED -							
PLOT DATE = 2/4/2008	DATE -	REVISED -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT • CHAMPAIGN & VERMILION CONTRACT NO. 70703	