

SCHEDULE OF PAINT PAVEMENT MARKING QUANTITIES

78001110 PAINT PAVEMENT MARKING - LINE 4 INCH

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>OFFSET</u>	<u>DESCRIPTION</u>	<u>LENGTH (FT)</u>
<u>LOCATION #1</u>		<u>SN 010-0183</u>			
898+76.00		903+82.00	EBCL	WHITE SKIP DASH	130.00
898+76.00		903+82.00	WBCL	WHITE SKIP DASH	130.00
898+76.00		903+82.00	EBDL	WHITE SOLID EDGE LINE	510.00
898+76.00		903+82.00	WBDL	WHITE SOLID EDGE LINE	510.00
<u>WHITE - LINE 4 INCH SUBTOTAL =</u>					<u>1280.00</u>
898+76.00		903+82.00	EBPL	YELLOW SOLID EDGE LINE	510.00
898+76.00		903+82.00	WBPL	YELLOW SOLID EDGE LINE	510.00
<u>YELLOW - LINE 4 INCH SUBTOTAL =</u>					<u>1020.00</u>
<u>LOCATION #2</u>		<u>SN 092-0148</u>			
1411+11.00		1416+17.00	EBCL	WHITE SKIP DASH	130.00
1411+11.00		1416+17.00	EBDL	WHITE SOLID EDGE LINE	510.00
<u>WHITE - LINE 4 INCH SUBTOTAL =</u>					<u>640.00</u>
1411+11.00		1416+17.00	EBPL	YELLOW SOLID EDGE LINE	510.00
<u>YELLOW - LINE 4 INCH SUBTOTAL =</u>					<u>510.00</u>
<u>WHITE - LINE 4 INCH TOTAL =</u>					<u>1920.00</u>
<u>YELLOW - LINE 4 INCH TOTAL =</u>					<u>1530.00</u>
<u>PAINT PAVEMENT MARKING - LINE 4 INCH TOTALS =</u>					<u>3450.00</u>

FILE NAME *	USER NAME = collierbw	DESIGNED - RTB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF PAINT PAVEMENT MARKING QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\projects\4578783\78783plans.dgn		DRAWN - JRP 12-14-07	REVISED -			74	(10-92-8,92-9)	*	13	8	
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			* CHAMPAIGN & VERMILION		CONTRACT NO. 70703			
PLOT DATE = 2/5/2008		DATE -	REVISED -			SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	