

SUMMARY OF QUANTITIES

LOCATION OF WORK:

F. A. U. 7123 (IL 10) CHAMPAIGN URBAN STA. 143+33.80 STA. 300+19.00 100% STATE F000	F. A. S. 1514 (IL 10) CHAMPAIGN RURAL STA. 300+19.00 STA. 381+99.11 100% STATE F000
---	---

CONSTRUCTION TYPE CODE:

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,300.0	4,120.0	2,180.0
40600300	AGGREGATE (PRIME COAT)	TON	125.0	80.0	45.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	790.0	515.0	275.0
67100100	MOBILIZATION	L SUM	1.0	0.6	0.4
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.6	0.4
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,730.0	3,095.0	1,635.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,575.0	1,030.0	545.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	55,155.0	36,065.0	19,090.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	296.0	193.0	103.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER <i>REMOVAL</i>	EACH	296.0	193.0	103.0
X0325223	FIBER ASPHALT	POUND	28,795.0	18,830.0	9,965.0
X4480205	MICRO-SURFACING, 2 PASSES, TYPE 2	SQ YD	63,040.0	41,225.0	21,815.0
* SPECIALTY ITEMS					

* FAU 7123 (IL 10)
FAS 1514 (IL 10)

FILE NAME = c:\projects\0570722\70722plan.dgn	USER NAME = p1ersonbr	DESIGNED - CRG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - BBP	REVISED -					*	09PPP	CHAMPAIGN	13	4
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -									
	PLOT DATE = 3/25/2008	DATE - 03/18/08	REVISED -									
											CONTRACT NO. 70722	
											FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	