

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CONTRACT NO. 72679

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	84-9RS-6 1/2 IGZ	SANGAMON	425	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

FAI 72 IM	FAU 8071 ACM	FAU 8071	FAU 8071	80% FED. 10% STATE 10% CITY FAU 8071 ACM
INTERCHANGE AND I-72	MACARTHUR BLVD (NORTH LEG)	MACARTHUR BLVD (NORTH LEG)	EXTRA WORK LEGACY POINTE DEVELOPMENT	BIKE TRAIL INTERURBAN
90% FED 10% STATE	URBAN 80% FED 20% STATE	LOCAL 100% LOCAL	LOCAL 100% LOCAL	

LOCATION OF WORK				CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	1000-2A	1000-2A	4047
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	763		381.5	381.5		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11300		5650	5650		
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	4579	4579				
44001980	CONCRETE BARRIER REMOVAL	FOOT	280					280
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	1367		439	439		489
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	56	56				
44200630	CLASS A PATCHES, TYPE II, 15 INCH	SQ YD	104	104				
44200631	CLASS A PATCHES, TYPE III, 15 INCH	SQ YD	32	32				
44213000	PATCHING REINFORCEMENT	SQ YD	507	507				
44213200	SAW CUTS	FOOT	3076	3076				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1537	1537				
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	6474					6474
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	3988	3988				
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	18162	13922.0	1290.5	1290.5	1659.0	
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	623	623				
54210300	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 15"	FOOT	204					204
54210309	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 24"	FOOT	66					66
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	1				4
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		0.5	0.5		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4					4
54214920	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 15"	EACH	8					8
54214929	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 24"	EACH	4					4
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	3673	257	1040	1040	1336	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	1156		352	352	452	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	57					57
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	142					142
55028900	STORM SEWERS, TYPE 5, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS V 48"	FOOT	210					210
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	47	47				
60102005	PIPE DRAINS 12" (SPECIAL)	FOOT	381	299	25	25	32	
60107600	PIPE UNDERDRAINS 4"	FOOT	14431	14431				

* - PAY ITEM REQUIRES A SPECIAL PROVISION

PLOT DATE = May-14-2008 07:00:00 AM
FILE NAME = D:\Projects\72679\84-9RS-6 1/2 IGZ\SUMQ.DGN
PLOT SCALE = 1/8"=1'-0"
USER NAME = joughlinr1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 72 (I-72)
SECTION 84-9RS-6 1/2 IGZ
SANGAMON COUNTY
SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____