

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

CONTRACT NO. 72679

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	184-91RS-61 (G)Z	SANGAMON	425	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

FAI 72 IM  
FAU 8071 ACM  
FAU 8071 LOCAL  
FAU 8071 LOCAL  
80% FED. 20% STATE  
100% LOCAL  
100% LOCAL  
BIKE TRAIL INTERURBAN

80% FED. 10% STATE 10% CITY  
FAU 8071 ACM

LOCATION OF WORK	INTERCHANGE AND I-72	MACARTHUR BLVD (NORTH LEG) URBAN	MACARTHUR BLVD (NORTH LEG) LOCAL	EXTRA WORK LEGACY POINTE DEVELOPMENT LOCAL	BIKE TRAIL INTERURBAN
	90% FED 10% STATE	80% FED 20% STATE	100% LOCAL	100% LOCAL	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				100% LOCAL
				I000-2A	I000-2A	I000-2A	I000-2A	
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1				
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	0.67	0.165	0.165		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	41	41				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6003	6003				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	29212	29212				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	426	426				
72000100	SIGN PANEL - TYPE 1	SQ FT	820	274	200.5	200.5		145
72000200	SIGN PANEL - TYPE 2	SQ FT	726	352	76.5	76.5	195	26
S 72000300	SIGN PANEL - TYPE 3	SQ FT	2525	2525				
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	962	962				
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	1358	1358				
72500300	OBJECT MARKER - TYPE 3	EACH	2					2
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	18157	18157				
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1943	775	461	461		246
73000100	WOOD SIGN SUPPORT	FOOT	90	90				
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	31	7	12	12		
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	80	80				
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	57	57				
73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	45	45				
73400100	CONCRETE FOUNDATIONS	CU YD	32	32				
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	10	10				
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1	1				
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1				
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	20	20				
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	20	20				
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	3	3				
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	438					438
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	132					132

100% LOCAL

PLT DATE = 11/14/2008 10:55:24AM  
PLT MAKE = C:\WINDOWS\SYSTEM32\cmd.exe  
PLT SCALE = 1/8"=1'-0"  
USER NAME = jhaughlin

**\*\* Specialty Items**  
 \* - PAY ITEM REQUIRES A SPECIAL PROVISION  
 S - SIGN PANEL - TYPE 3 PAID FOR AS 100% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAI 72 (I-72)  
SECTION 184-91RS-61 (G)Z  
SANGAMON COUNTY

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_