

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CONTRACT NO. 72679

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-9RS-6) (G)Z	SANGAMON	425	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

FAI 72
IM

FAU 8071
ACM

FAU 8071

FAU 8071

80% FED.
10% STATE
10% CITY
FAU 8071
ACM

LOCATION OF WORK	INTERCHANGE AND I-72	MACARTHUR BLVD (NORTH LEG)	MACARTHUR BLVD (NORTH LEG)	EXTRA WORK LEGACY POINTE DEVELOPMENT	BIKE TRAIL INTERURBAN
	90% FED 10% STATE	URBAN 80% FED 20% STATE	LOCAL 100% LOCAL	LOCAL 100% LOCAL	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				7047
				I000-2A	I000-2A	I000-2A	I000-2A	
87800410	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER (SPECIAL)	FOOT	30	10			20	
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNT	EACH	9	4	2	2	1	
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNT	EACH	54	12	2	2	38	
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNT	EACH	2		1	1		
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNT	EACH	5	2			3	
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNT	EACH	4		1	1	2	
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNT	EACH	9	6		1	3	
88040250	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-4-SECTION, BRACKET MOUNT	EACH	2		1	1		
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNT	EACH	9	1	1	1	6	
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3				3	
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3-SECTION, 2-5-SECTION, BRACKET MOUNTED	EACH	2				2	
88040360	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2	
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	13		2	2	9	
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	5		0.5	0.5	4	
88102850	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, BRACKET MOUNTED	EACH	3				3	
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	83	12	5	5	61	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	29		3	3	23	
K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1					1
X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	44	44				
X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	7	2	0.5	0.5	4	
X0322279	OUTLET MARKER	EACH	44	44				
X0322472	RADIUS GUARDRAIL	EACH	4	4				
X0322729	MATERIAL TRANSFER DEVICE	TON	21814	13363	2572	2572	3307	
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	5827	2443	674	674	2036	
X0325610	PAVEMENT REPLACEMENT, SURFACE COURSE	SQ YD	763		381.5	381.5		
X2503000	MAINTENANCE MOWING	ACRE	10	10				
X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	25512	25512				
X8170245	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 12	FOOT	3945				3945	
XX004350	TRANSVERSE DRAINS COMPLETE	EACH	15	11	2	2		

PLT DATE: 11/14/2008 07:40:20AM
FILE NAME: C:\Users\jv\Documents\11111111.dwg
USER NAME: jv
PLOT DEVICE: HP DesignJet 5000PS

** Specialty Items
* - PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 72 (I-72)
SECTION (84-9RS-6) (G)Z
SANGAMON COUNTY
SCALE: VERT. DATE
HORIZ. DATE
DRAWN BY
CHECKED BY