

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-9)RS-6; (G)Z	SANGAMON	425	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SHOULDER RUMBLE STRIP

LOCATION	LENGTH (FOOT)
I-72 MAINLINE	
EASTBOUND OUTSIDE SHOULDER	
STA 553+65.00 TO STA 571+05.03 BK	1,740.03
STA 569+30.74 AH TO STA 576+12.70	681.96
STA 576+12.70 TO STA 583+43.20	0.00
STA 583+43.20 TO STA 606+81.87	2,338.67
STA 609+73.10 TO STA 611+88.70	215.60
STA 611+88.70 TO STA 623+49.20	0.00
STA 623+49.20 TO STA 628+40.00	490.80
EASTBOUND INSIDE SHOULDER	
STA 553+65.00 TO STA 571+05.03 BK	1,740.03
STA 569+30.74 AH TO STA 606+81.87	3,751.13
STA 609+73.10 TO STA 628+40.00	1,866.90
WESTBOUND OUTSIDE SHOULDER	
STA 553+65.00 TO STA 571+05.03 BK	1,740.03
STA 569+30.74 AH TO STA 569+89.10	58.36
STA 569+89.10 TO STA 582+09.80	0.00
STA 582+09.80 TO STA 607+28.96	2,519.16
STA 610+29.87 TO STA 616+51.20	621.33
STA 616+51.20 TO STA 625+50.30	0.00
STA 625+50.30 TO STA 628+40.00	289.70
WESTBOUND INSIDE SHOULDER	
STA 553+65.00 TO STA 571+05.03 BK	1,740.03
STA 569+30.74 AH TO STA 607+28.96	3,798.22
STA 610+29.87 TO STA 628+40.00	1,810.13
<b>TOTAL</b>	<b>25,402.08</b>

FENCE

LOCATION	WOVEN WIRE FENCE REM (FOOT)	WOVEN WIRE FENCE 4' (FOOT)
I-72 EASTBOUND		
STA 555+16 TO STA 571+05 BK	1,591	1,591
STA 569+31 AH TO STA 578+11	881	881
STA 623+49 TO STA 635+79 BK	1,212	1,212
STA 634+03 AH TO STA 647+75	1,384	1,384
I-72 WESTBOUND		
STA 623+56 TO STA 635+79 BK	1,258	1,258
STA 634+03 AH TO STA 647+75	1,387	1,387
<b>TOTAL</b>	<b>7,713</b>	<b>7,713</b>

MAINTENANCE MOWING

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	NUMBER OF MOWINGS	AREA (ACRES)
I-72 MAINLINE				
EASTBOUND				
STA 553+65 TO STA 571+05 BK	1,740	15	2	1.20
STA 569+31 AH TO STA 628+40	5,909	15	2	4.07
OUTSIDE				
STA 553+65 TO STA 571+05 BK	1,740	20	2	1.60
STA 569+31 AH TO STA 576+13	682	20	2	0.63
STA 623+49 TO STA 628+40	491	20	2	0.45
I-72 MAINLINE				
WESTBOUND				
STA 553+65 TO STA 571+05 BK	1,740	15	2	1.20
STA 569+31 AH TO STA 628+40	5,909	15	2	4.07
OUTSIDE				
STA 553+65 TO STA 571+05 BK	1,740	20	2	1.60
STA 569+31 AH TO STA 569+89	58	20	2	0.05
STA 625+50 TO STA 628+40	290	20	2	0.27
<b>TOTAL</b>				<b>9.87</b>

DELINEATORS

LOCATION	RADIUS (FOOT)	SPACING (FOOT)	IN CURVE (EACH)	ADVANCE (EACH)	BEYOND (EACH)	TOTAL (EACH)
I-72 MAINLINE						
EASTBOUND						
STA 582+82 TO STA 602+92	3,797	175	12			12
WESTBOUND						
STA 581+61 TO STA 607+29	3,797	175	15			15
<b>TOTAL</b>						<b>27</b>

PLOT DATE = Mar-19-2008 11:27:44AM  
 FILE NAME = C:\Projects\48555802\shoch.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAI 72 (I-72)  
 SECTION (84-9)RS-6; (G)Z  
 SANGAMON COUNTY  
 SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_