CONTRACT NO. 72679

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-9)RS-6; (G)Z	SANGAMON	425	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URETHANE PAVEMENT MARKING TYPE 2 - LINE 5"

LOCATION			COLOR	LENGTH (FOOT)
I-72 MAINLINE				
EASTBOUND				
OUTSIDE				
STA 553+65.00	TO	STA 571+05.03 BK	WHITE	1,740.0
STA 569+30.74 AH	TO	STA 576+12.70	WHITE	682.0
STA 582+81.90	TO	STA 606+81.87	WHITE	2,400.0
STA 609+73.10	TO	STA 611+88.70	WHITE	215.6
STA 623+49.20	TO	STA 628+40.00	WHITE	490.8
INSIDE				
STA 553+65.00	TO	STA 571+05.03 BK	YELLOW	1,740.0
STA 569+30.74 AH	TO	STA 606+81.87	YELLOW	3,751.1
STA 609+73.10	TO	STA 628+40.00	YELLOW	1,866.9
WESTBOUND				
OUTSIDE				
STA 553+65.00	TO	STA 571+05.03 BK	WHITE	1,740.0
STA 569+30.74 AH	TO	STA 569+89.10	WHITE	58.4
STA 581+61.30	TO	STA 607+28.96	WHITE	2,567.7
STA 610+29.87	TO	STA 616+51.20	WHITE	621.3
STA 625+50.30	TO	STA 628+40.00	WHITE	289.7
INSIDE				
STA 553+65.00	TO	STA 571+05.03 BK	YELLOW	1,740.0
STA 569+30.74 AH	TO	STA 607+28.96	YELLOW	3,798.2
STA 610+29.87	TO	STA 628+40.00	YELLOW	1,810.1
TOTAL				25,511.8

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"

LOCATION			LENGTH (FOOT)
I-72 MAINLINE			
EASTBOUND			
STA 553+65.00	TO	STA 571+05.03 BK	440.00
STA 569+30.74 AH	TO	STA 606+81.87	940.00
STA 609+73.10	TO	STA 628+40.00	470.00
WESTBOUND			
STA 553+65.00	TO	STA 571+05.03 BK	440.00
STA 569+30.74 AH	TO	STA 607+28.96	950.00
STA 610+29.87	TO	STA 628+40.00	460.00
TOTAL			3,700.00

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION			COLOR	EACH
I-72 MAINLINE				
EASTBOUND				
STA 553+65.00	TO	STA 571+05.03 BK	C	44
STA 569+30.74 AH	TO	STA 606+81.87	C	94
STA 609+73.10	TO	STA 628+40.00	C	48
WESTBOUND				
STA 553+65.00	TO	STA 571+05.03 BK	C	44
STA 569+30.74 AH	TO	STA 607+28.96	C	96
STA 610+29.87	TO	STA 628+40.00	C	46
TOTAL				372

SHORT TERM PAVEMENT MARKING

LOCATION			CENTERLINE WHITE (FOOT)	SHOULDER YELLOW (FOOT)	SHOULDER WHITE (FOOT)	TOTAL (FOOT)
I-72 MAINLINE						
EASTBOUND						
STA 553+65.00	TO	STA 571+05.03 BK	348.00	208.80	208.80	765.60
STA 569+30.74 AH	TO	STA 576+12.70	136.40	81.90	81.90	300.20
STA 576+12.70	TO	STA 582+81.90	133.80	80.40		214.20
STA 582+81.90	TO	STA 606+81.87	480.00	288.00	288.00	1,056.00
STA 609+73.10	TO	STA 611+88.70	43.20	25.80	25.80	94.80
STA 611+88.70	TO	STA 623+49.20	232.20	139.20		371.40
STA 623+49.20	TO	STA 628+40.00	98.20	58.80	58.80	215.80
WESTBOUND						
STA 553+65.00	TO	STA 571+05.03 BK	348.00	208.80	208.80	765.60
STA 569+30.74 AH	TO	STA 569+89.10	11.60	6.90	6.90	25.40
STA 569+89.10	TO	STA 581+61.30	234.40	140.70		375.10
STA 581+61.30	TO	STA 607+28.96	513.60	308.10	308.10	1,129.80
STA 610+29.87	TO	STA 616+51.20	124.20	74.70	74.70	273.60
STA 616+51.20	TO	STA 625+50.30	179.80	108.00		287.80
STA 625+50.30	TO	STA 628+40.00	58.00	34.80	34.80	127.60
TOTALS			2,941.40	1,764.90	1,296.60	6,002.90

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION				TOTAL (FOOT)
I-72 MAINLINE				
EASTBOUND				
STA 553+65.00	TO	STA 571+05.03 BK	IS, OS	58.0
STA 569+30.74 AH	TO	STA 576+12.70	IS, OS	22.8
STA 576+12.70	TO	STA 582+81.90	IS	11.2
STA 582+81.90	TO	STA 606+81.87	IS, OS	80.0
STA 609+73.10	TO	STA 611+88.70	IS, OS	7.2
STA 611+88.70	TO	STA 623+49.20	IS	19.4
STA 623+49.20	TO	STA 628+40.00	IS, OS	16.4
WESTBOUND				
STA 553+65.00	TO	STA 571+05.03 BK	IS, OS	58.0
STA 569+30.74 AH	TO	STA 569+89.10	IS, OS	2.0
STA 569+89.10	TO	STA 581+61.30	IS	19.6
STA 581+61.30	TO	STA 607+28.96	IS, OS	85.6
STA 610+29.87	TO	STA 616+51.20	IS, OS	20.8
STA 616+51.20	TO	STA 625+50.30	IS	15.0
STA 625+50.30	TO	STA 628+40.00	IS, OS	9.6
TOTALS				425.6

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAI 72 (I-72)
SECTION (84-9)RS-6; (G)Z
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Mar-19-2008 11:27:08AM
FILE NAME = C:\Projects\d855082\shtech.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = laughlrr1