

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	62
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9) RS-6; IGZ *				



© Copyright Hanson Professional Services Inc. 2008

LAYOUT CLG 09/17/07
 DRAWN CLG 09/17/07
 REVIEWED JMW 03/12/08
 Mar-20-2008 07:47:04AM
 \$FILE*

PIPE UNDERDRAIN SCHEDULE						
LOCATION		HEAVY DUTY EXCELSIOR BLANKET	CONCRETE HEADWALL FOR PIPE DRAINS	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	TRANSVERSE DRAINS COMPLETE
BEGIN STATION	END STATION / OFFSET	SQ YD	EACH	FOOT	FOOT	EACH
MACARTHUR BOULEVARD						
771+50.00		36				1
776+00.00		36				1
781+10.00		36				1
786+00.00		36				1
789+00.00		36				1
806+10.00		36				1
811+00.00		36				1
816+00.00		36				1
820+00.00		36				1
SUBTOTAL		324				9
RAMP A						
10+00.00	17.71 RT	18	1		18	
10+00.00	14+20.00 RT			420		
10+00.00						18
10+06.00	21.10 RT	18	1			
14+20.00	19+00.00 RT			480		
14+20.00						15
16+60.00	19+75.00 LT			315		
17+19.94	17.20 RT	18	1		52	
19+00.00	12.94 RT	36	2			
19+00.00	21+00.00 RT			200		
19+00.00	SAG RT					13
19+00.00	SAG RT					13
19+75.00	33.06 LT	36	2			
19+75.00	21+00.00 LT			125		
19+75.00						17
19+75.00						17
21+00.00	12.93 RT	18	1			13
21+00.00	31.94 LT	18	1			13
21+00.00	26+00.00 RT			500		
21+00.00	26+00.00 LT			506		
22+00.00		36				1
25+50.00		36				1
26+00.00	19.53 RT	18	1		17	
26+00.00	41.57 LT	18	1		15	
26+00.00	29+84.00 RT			395		
26+00.00	29+40.00 LT			334		
SUBTOTAL		270	11	3274	219	2
RAMP B						
20+78.00	25+05.29 RT			436		
20+95.00	25+05.29 LT			401		
24+00.00		36				1
25+05.29	15.85 RT	36	2			
25+05.29	43.26 LT	36	2			
25+05.29	30+00.00 RT			495		
25+05.29	30+00.00 LT			481		
25+05.29	SAG RT					16
25+05.29	SAG RT					16
25+05.29	SAG LT					13
25+05.29	SAG LT					13
30+00.00	15.47 RT	18	1		15	
30+00.00	33.56 LT	18	1		13	
30+00.00	31+50.00 RT			150		
30+00.00	31+50.00 LT			150		
36+50.00	40+00.00 RT			350		
36+50.00	38+00.00 LT			150		
38+00.00	14.98 RT	18	1		32	
38+70.00	15.86 RT	18	1		45	
40+00.00	15.47 RT	18	1		15	
40+00.00	45+00.00 RT			500		
45+00.00	14.20 RT	18	1		14	
45+00.00	50+35.00 RT			535		
50+35.00	18.15 RT	18	1		18	
50+41.35	18.77 RT	18	1		20	
SUBTOTAL		252	12	3648	230	1
RAMP C						
30+00.00	13.49 RT	18	1		14	
30+16.00	15.98 RT	18	1		16	
30+15.00	35+00.00 RT			485		
35+00.00	14.88 RT	18	1		15	
35+00.00	40+00.00 RT			500		
39+60.00	15.75 RT	18	1		55	
40+00.00	14.58 RT	18	1			
40+00.00	43+50.00 RT			350		
40+00.00	43+50.00 LT			353		
40+00.00						14
40+00.00	LT TO RT					31
48+50.00	50+00.00 RT			150		
48+50.00	50+00.00 LT			150		
48+50.00	SAG RT					74

PIPE UNDERDRAIN SCHEDULE						
LOCATION		HEAVY DUTY EXCELSIOR BLANKET	CONCRETE HEADWALL FOR PIPE DRAINS	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	TRANSVERSE DRAINS COMPLETE
BEGIN STATION	END STATION / OFFSET	SQ YD	EACH	FOOT	FOOT	EACH
48+50.00	SAG RT					74
50+00.00	15.36 RT	36	2			
50+00.00	36.30 LT	36	2			
50+00.00	54+00.00 RT			400		
50+00.00	54+00.00 LT			403		
50+00.00	SAG RT					15
50+00.00	SAG RT					15
50+00.00	SAG LT					14
50+00.00	SAG LT					14
52+50.00		36				1
54+00.00	21.79 RT	18	1			
54+00.00	43.88 LT	18	1			
54+00.00	57+35.00 RT			357		
54+00.00	57+17.00 LT			317		
54+00.00						15
54+00.00						13
SUBTOTAL		234	11	3465	380	1
RAMP D						
40+73.62	45+00.00 RT			437		
40+81.21	45+00.00 LT			419		
45+00.00	15.95 RT	18	1		16	
45+00.00	29.26 LT	18	1		13	
45+00.00	50+00.00 RT			500		
45+00.00	50+00.00 LT			496		
46+00.00		36				1
50+00.00	14.20 RT	18	1		14	
50+00.00	12.15 LT	18	1		12	
50+00.00	54+50.00 RT			450		
50+00.00	54+50.00 LT			450		
51+00.00		36				1
54+50.00	13.88 RT	36	2			
54+50.00	32.41 LT	18	1			
54+50.00	58+50.00 RT			400		
54+50.00	SAG RT					14
54+50.00	SAG RT					14
54+50.00	SAG LT					16
55+28.00	20.88 RT	18	1		61	
58+50.00	60+25.00 RT			175		
60+25.00	17.72 RT	36	2			
60+25.00	64+00.00 RT			375		
60+25.00	SAG RT					18
60+25.00	SAG RT					18
64+00.00	17.72 RT	18	1		18	
64+00.00	67+41.62 RT			342		
67+41.62	16.61 RT	18	1		16	
67+51.59	17.94 RT	18	1		19	
SUBTOTAL		306	13	4044	247	2
TOTAL		1386	47	14431	1075	15

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES -2
 FAI-72, MACARTHUR BLVD
 SECTION
 (84-9) RS-6; (G)Z
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. _____
 HORIZ. _____
 DATE: Mar-20-2008 07:47:04AM
 DRAWN BY: CLG
 CHECKED BY: MH