CONTRACT # 72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	64
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6; (G)Z *

PAVING SCHEDULE

LOCATION			SHAPING AND GRADING ROADWAY	PROCESSING MODIFIED SOILS 12"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE A	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	AGGREGATE BASE COURSE, TYPE A 6"	AGGREGATE BASE REPAIR	AGGREGATE SURFACE COURSE, TYPE A 8"	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	SEAL COAT AGGREGATE	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"
			UNIT	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	TON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD
BEGIN STATION	**END STATION**	**OFFSET**																		
RAMP C																				
30+00.00	30+76.88	LT&RT					92													
30+76.88	34+10.00	LT&RT					638													
34+10.00	35+50.00	LT&RT					412													
35+50.00	39+00.00	LT&RT					1506													
30+00.00	57+59.13	LT&RT		1851.00													799			7120
39+00.00	39+60.00	LT				8.6														
39+00.00	44+85.98		6																	
47+15.09	57+59.13		10																	
47+40.56	57+46.54	LT&RT		5885.00																
ROADWAY TOTAL					154.7															
		SUBTOTAL	**16**	**7736.00**	**154.7**	**8.6**	**2648**										**799**			**7120**
RAMP D																				
40+41.50	67+51.59	LT&RT		5470.00	109.4												561			5009
40+41.50	55+75.00		15																	
55+25.00	55+75.00	LT				7.1														
55+75.00	59+01.29	LT&RT					1153													
59+01.29	66+01.59	LT&RT					1381													
66+01.59	67+51.59	LT&RT					179													
		SUBTOTAL	**15**	**5470.00**	**109.4**	**7.1**	**2713**										**561**			**5009**
INTERURBAN TRAIL																				
10+53.40	23+00.00								1442					2.4	236.3					
11+40.00	24+87.00		13																	
12+57.47	Parking lot								1169					1.6	194.9					
23+00.00	37+84.91								1263					2.0	203.8					
27+18.00	37+91.93		9																	
37+67.86	37+84.91														3.2					
50+00.00	52+75.05	PARK LOT	3																	
		SUBTOTAL	**25**						**3874**					**6.0**	**638.2**					
RECREATION DRIVE																				
100+33.00	101+90.57	LT&RT		768.00														756		
100+33.00	127+25.00		27																	
101+90.57	127+25.00	LT&RT		9011.00														6758		
115+00.00		LT									118									
115+00.00		RT									118									
126+15.40		LT									118									
126+85.20		LT									28									
ROADWAY TOTAL					195.6															
		SUBTOTAL	**27**	**9779.00**	**195.6**						**382**							**7514**		
LINCOLNSHIRE BOULEVARD																				
180+51.04	183+95.21	LT&RT		2391.33													433		3864	
ROADWAY TOTAL					47.8															
		SUBTOTAL		**2391.33**	**47.8**												**433**		**3864**	
CENTRE STREET																				
10+08.78	10+75.50	LT&RT		419.00														361		
10+08.78	13+62.02		4																	
10+75.50	12+61.03	LT&RT		663.00														557		
12+61.03	13+62.02	LT&RT		609.00														522		
	10+42.00	RT							83					0.1	14.0					
	10+44.00	LT							87					0.1	14.0					
ROADWAY TOTAL					33.8															
		SUBTOTAL	**4**	**1691.00**	**33.8**				**170**					**0.2**	**28.0**			**1440**		
WEST GRAND AVENUE																				
523+24.03	525+90.76	LT&RT		978.00	19.9					850		11.2	79.0	5.2		1120	110		978	
		SUBTOTAL		**978.00**	**19.9**					**850**		**11.2**	**79.0**	**5.2**		**1120**	**110**		**978**	
HAZEL DELL																				
ROADWAY RESURFACING TOTAL										350		4.6	33.0	2.1		460				
		SUBTOTAL								**350**		**4.6**	**33.0**	**2.1**		**460**				
		TOTAL	**218**	**149600.78**	**2992.3**	**29.6**	**10051**	**3322.25**	**4044**	**1200**	**544**	**15.8**	**112.0**	**13.8**	**666.2**	**1580**	**13029**	**8954**	**91833**	**24495**

© Copyright Hanson Professional Services Inc. 2008

HANSON

Mar-20-2008 07:47:10AM
$FILE$

LAYOUT	CLG	09/17/07
DRAWN	CLG	09/17/07
REVIEWED	JWM	03/12/08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES -4
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6; (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT.
HORIZ.
DATE Mar-20-2008 07:47:10AM

DRAWN BY CLG
CHECKED BY MH