CONTRACT #72679

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	67
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9) RS-6; (G)Z *

CONCRETE CURB, CURB AND GUTTER, MEDIAN AND BRIDGE APPROACH PAVEMENT SCHEDULE

LOCATION			BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT	BRIDGE APPROACH PAVEMENT (SPECIAL)	APPROACH PAVEMENT SPECIAL	CLASS SI CONCRETE (OUTLET)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (VARIABLE WIDTH GUTTER FLAG)	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB-6.12	CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL)	CONCRETE MEDIAN, TYPE SM-6.12
			SQ YD	SQ YD	SQ YD	SQ YD	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ FT	SQ FT
BEGIN STATION	END STATION	OFFSET																
833+69.00		LT		6														
836+94.50	838+77.88	R TO L		33				183.5										
838+77.88	842+38.88			240													2162.0	
842+51.99	842+70.11	L		7									21.0					
842+67.00		LT		13														
843+23.56	843+41.41	L		15										23.5				
843+29.00		LT		6														
847+96.90	849+79.93	R TO L		33				183.0										
849+79.93	851+87.93			138													1244.0	
852+00.29	852+19.31	L		7									22.0					
852+14.00		LT		13														
852+77.93	853+09.54	L		22										37.0				
852+84.00		LT		10														
862+82.30	864+42.72	R TO L		29				161.0										
864+42.72	865+90.62			98													884.0	
867+18.18	868+21.84			69													621.0	
868+21.84	869+82.26	R TO L		29				160.0										
874+07.50	875+65.00	R		29				157.0										
875+65.00	877+36.80			115													1033.0	
		SUBTOTAL		**17000**	**1429**			**2199.5**	**19019.5**	**12374.0**	**129.5**	**82.0**	**168.0**	**149.5**	**30375.0**	**936.0**	**10548.0**	
RAMP A																		
27+00.00		LT		10			2.1											
27+00.00		RT		10			2.1											
27+26.00	27+34.00	R		3						8.0								
27+27.28	27+35.90	L		3						8.0								
27+34.00	28+52.00	R		35					118.0									
27+35.90	29+82.71	L		75					256.0									
28+57.00		RT		10														
28+62.00	30+31.71	R		61					209.0									
29+83.20	29+94.20	L		4									11.0					
		SUBTOTAL		**211**			**4.2**		**583.0**	**16.0**			**11.0**					
RAMP B																		
20+53.00	32+33.50	L		340					1160.0									
20+53.83	20+67.84	R		6									17.0					
20+59.00	21+83.50	R		49					166.0									
21+88.50		RT		10														
21+93.50	24+95.00	R		89					304.0									
25+00.00		RT		10														
25+05.00	29+75.00	R		139					474.0									
29+80.00		RT		10														
29+85.00	31+99.90	R		63					215.0									
32+07.97	32+37.97		90	90														
35+52.79	35+82.79		90	90														
35+76.30	37+45.00	R		49					168.5									
37+50.00		RT		10														
37+55.00	39+35.10	R		53					180.0									
39+40.00		RT		10														
39+45.00	41+25.00	R		53					180.0									
41+30.00		RT		10														
41+35.00	42+65.30	R		38					131.0									
42+65.30	42+73.20	R		3						8.0								
43+00.00		RT		10			2.1											
		SUBTOTAL	**180**	**1132**			**2.1**		**2978.5**	**8.0**			**17.0**					
RAMP C																		
35+50.00		RT		10			2.1											
35+76.80	35+84.80	R		3						8.0								
35+84.80	38+45.00	R		76					260.5									
38+50.00		RT		10														
38+55.00	41+45.00	R		85					290.0									
41+50.00		RT		10														
41+55.00	44+53.30	R		88					298.5									
44+56.54	44+86.54		90	90														
47+14.56	47+44.56		89	89														
47+42.50	50+05.00	R		77					262.5									
47+51.20	57+47.63	L		296					1009.0									
50+10.00		RT		10														
50+15.00	50+57.00	R		12					42.0									
50+62.00		RT		10														
50+67.00	53+45.00	R		82					278.0									
53+50.00		RT		10														

© Copyright Hanson Professional Services Inc. 2008

HANSON

Mar-20-2008 07:47:54AM
$FILE$

LAYOUT	CLG	09/17/07
DRAWN	CLG	09/17/07
REVIEWED	JMM	03/12/08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES -7
FAI-72, MACARTHUR BLVD
SECTION
(84-9) RS-6; (G)Z
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ.
DATE Mar-20-2008 07:47:15AM
DRAWN BY CLG
CHECKED BY MH