

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	425	70
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9) RS-6; (G)Z *				

EROSION CONTROL SCHEDULE

LOCATION	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	STONE RIPRAP, CLASS B3
	POUND	EACH	FOOT	EACH	SQ YD
MACARTHUR BOULEVARD					
769+31.49			179.00		
769+60.00	200				
783+00.00		12			
785+00.00			127.10		
797+35.00			93.10		
798+08.49	400				
798+08.49			53.00		
798+44.00			126.00		
798+08.49		16			
800+52.50				15	
818+50.00			199.00		
818+50.00			213.50		
819+53.81	50				
820+75.00			425.00		
823+00.00				31	
822+50.00			214.20		
841+29.00			168.20		
841+00.00		8			
866+80.00			660.60		
868+00.00			220.20		
770+00.36				1	
770+75.00				1	
786+20.00				1	
790+20.00				1	
794+20.00				1	
SUBTOTAL	650	36	2678.90	51	
RAMP A					
18+80.00			390.00		
12+00.00		3			
25+50.00			399.10		
10+00.00				1	
12+00.00				1	
14+20.00				1	
15+00.00				1	
15+81.00				1	
21+00.00				1	
SUBTOTAL		3	789.10	6	
RAMP B					
20+00.00		2			
28+00.00		14			
33+50.00			591.70		
42+50.00		1			
25+00.00				1	
36+50.00				1	
SUBTOTAL		17	591.70	2	
RAMP C					
30+00.00			255.60		
30+00.00		3			
43+00.00		10			
44+65.00	1			1	
44+84.00				1	
46+50.00				2	
50+62.00					6
50+98.50				1	
SUBTOTAL		13	255.60	5	6
RAMP D					
40+00.00		7			
42+25.00			2553.90		
52+00.00				1	
SUBTOTAL		7	2553.90	1	
MACARTHUR STORM SEWER					
108+62.40				1	
111+42.00				1	
SUBTOTAL				2	
RECREATION DRIVE					
100+95.00			636.20		
105+50.00			377.20		
115+20.00				1	
115+20.00				1	
124+00.00			162.60		
104+20.00				1	
125+22.80				1	
126+45.00				1	
SUBTOTAL			1176.00	5	
LINCOLNSHIRE BOULEVARD					
180+70.70			303.68		
SUBTOTAL			303.68		

EROSION CONTROL SCHEDULE

LOCATION	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	STONE RIPRAP, CLASS B3
	POUND	EACH	FOOT	EACH	SQ YD
WEST GRAND AVENUE					
181+45.00					4
SUBTOTAL					4
CENTRE STREET					
10+60.00			285.60		1
10+60.00			300.60		
SUBTOTAL			586.20		1
INTERURBAN TRAIL PARKING LOT					
					1
SUBTOTAL					1
TOTAL	650	76	8935.08	78	6

© Copyright Hanson Professional Services Inc. 2008



LAYOUT CLG 09/17/07
 DRAWN CLG 09/17/07
 REVIEWED JMW 03/12/08
 Mar-20-2008 07:47:24AM \$FILE*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES -10
 FAI-72, MACARTHUR BLVD
 SECTION
 (84-9) RS-6; (G)Z
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY MH
 DATE Mar-20-2008 07:47:24AM